

PRELIMINARY SITE EVALUATION REPORT

Remedial Investigation/Feasibility Study Eagle Zinc Company Site, Hillsboro, Illinois

Submitted To:

U.S. Environmental Protection Agency, Region V and Illinois Environmental Protection Agency

Submitted By:

ENVIRON International Corporation Deerfield, Illinois

On behalf of

Eagle Zinc Group

March 2002

CONTENTS

		<u>Page</u>
I.	INTRODUCTION	1
II.	PHYSICAL SETTING	2
III.	ENVIRONMENTAL SETTING A. Climate B. Topography and Hydrology C. Soils D. Geology E. Hydrogeology	4 4 4 5 6 7
IV.	SITE HISTORY AND OPERATIONS A. Site History B. Description of Historical Operations C. General Description of Zinc Oxide Manufacturing Process D. Description of Current Processes E. Residual Materials	9 9 11 11 12 13
V.	REGULATORY HISTORY	15
VI.	EVALUATION OF EXISTING DATA A. Soil B. Sediment C. Residues D. Surface Water E. Ground Water	18 18 19 20 21 22
VII.	SITE ACCESS	23
VIII.	SITE CONCEPTUAL MODEL	24
IX	PREPARATION OF SUPPORT FACILITIES	25

-i- ENVIRON

CONTENTS

(Continued)

TABLES

Table 1: Summary of Historical Site Investigations
 Table 2: Historical Sampling Results- Off-Site Soil
 Table 3: Historical Sampling Results- On-Site Soil
 Table 4: Historical Sampling Results- Sediment
 Table 5: Historical Sampling Results- Residues
 Table 6: Historical Sampling Results- Storm Water
 Table 7: Historical Sampling Results- Ground Water

FIGURES

Figure 1:	Site Location Map
Figure 2:	Site Layout Map
Figure 3:	Topographic Survey Map
Figure 4:	Shallow Ground Water Contour Map
Figure 5:	Previous Sampling Locations- Off-Site Soil
Figure 6:	Previous Sampling Locations- On-Site Soil
Figure 7:	Previous Sampling Locations- Sediment
Figure 8:	Previous Sampling Locations- Residues
Figure 9:	Previous Sampling Locations- Storm Water
Figure 10:	Potential Areas of Concern: On-Site Soil
Figure 11:	Potential Areas of Concern: Sediment
Figure 12:	Potential Areas of Concern: Residues
Figure 13:	Potential Areas of Concern: Surface Water
Figure 14:	Potential Areas of Concern: Ground Water

ATTACHMENTS

Attachment A: Results of ENVIRON Well Search Attachment B: Results of Previous Well Searches Attachment C: Historical Aerial Photographs Attachment D: Site History Timeline

I. INTRODUCTION

This Preliminary Site Evaluation (PSE) Report details background information and environmental conditions pertinent to the Eagle Zinc Company site (the "Site"), located in Hillsboro, Illinois. The PSE was conducted by ENVIRON International Corporation (ENVIRON) on behalf of the Eagle Zinc Group (the "Group") as the initial task associated with the Remedial Investigation/Feasibility Study (RI/FS) for the Site. The RI/FS is being completed pursuant to the Statement of Work (SOW) within the Administrative Order on Consent (AOC) between the Group and the U.S. Environmental Protection Agency (USEPA) dated December 31, 2001.

The purpose of the RI is to investigate the Site's physical characteristics, identify sources of contamination, and determine the nature and extent of contamination at the Site. The purpose of the FS is to develop and evaluate remedial action alternatives based on the RI data and report.

Subsequent sections of this PSE report present a discussion of:

- Physical Setting (Section II);
- Environmental Setting (Section III);
- Site History and Current Operations (Section IV);
- Regulatory History (Section V);
- Evaluation of Existing Data (Section VI);
- Site Inspection and Access (Section VII);
- Site Conceptual Model (Section VIII); and
- Preparation of Support Facilities (Section IX).

II. PHYSICAL SETTING

The Site is located in the Township of Hillsboro, Illinois. Hillsboro is located in central Montgomery County, Illinois, approximately 50 miles northeast of St. Louis, Missouri and 35 miles south of Springfield, Illinois. The Site is approximately 132 acres in size and is defined as the parcels of land currently owned by Eagle Zinc Company. The Site is situated on two adjoining tracts of land in the Southeast quarter of Section 1 and the Northeast quarter of Section 12, Township 8 North, Range 4 West, as well as part of the Southwest quarter of Section 6, Township 8 North, Range 3 West of the 3rd Principal Meridian.

Figure 1 presents a portion of the U.S. Geological Survey Hillsboro, Illinois 7.5-minute quadrangle, indicating the location of the Site property. Figure 2 is a generalized Site layout map. The Site was surveyed in June 1998 by Hurst-Roche Engineers Inc. (HR Engineers), including a boundary survey and a topographic survey that covers the majority of the Site (Figure 3). The topographic contour map will be completed to include the entire Site property and will be used as the base map for the project. As specified in the SOW, all sample location (grid) maps will be produced as overlays to the general base map.

The Site is located in a mixed commercial/industrial/residential area located in the northeastern part of Hillsboro. The Site extends from Smith Road south to an unnamed tributary to the Middle Fork of Shoal Creek. Industrial Drive extends north and south along much of the eastern property boundary. North of the Site is Smith Street a small facility called Hayes Abrasives, a golf course, and farm fields. Industrial Drive, an asphalt company, a railroad corridor, and the former Hillsboro Glass Company facility (now a steel warehouse) are located east of the Site. Some small commercial/industrial facilities (University of Illinois Extension office, Fuller Brothers Construction/Ready Mix, Illinois Wood Preservers, Hillsboro Rental, Vogel Plumbing) are located south of the Site. Some undeveloped land and a residential area containing single- and multifamily dwellings are located west of the Site. The nearest residential properties are located approximately 200 feet west of the southern and central part of the Site's buffer zone.

It is estimated that between 10 and 15 percent of the Site is covered by buildings. Approximately 23 buildings currently exist at the Site, some of which are currently unused or are used only for storage purposes. The types of buildings currently used for facility operations include the office/laboratory building, manufacturing/processing buildings, equipment/raw material/finished product storage buildings, baghouses, and maintenance facilities. Other Site features include railroad spurs, raw material and

residual material stockpiles, two storm water detention ponds, a small pond in the southeast corner of the property, and several paved and unpaved roadways.

III. ENVIRONMENTAL SETTING

A. Climate

The following information on the climate of Hillsboro, Illinois was obtained from on-line sources of historical weather data. The climate of Montgomery County is considered continental and temperate. The summer months are hot and humid with an average temperature of 75° Fahrenheit (F) and an average daily high temperature of 87° F. The winter months are moderately cool with an average temperature of 31° F and an average daily high temperature of 40° F. Rainfall is well distributed throughout the year, with the highest average rainfall in May. Total annual precipitation for the area is approximately 41 inches. Approximately 57 percent, or 23 inches, of the total annual precipitation occurs as rain from April through September and coincides with the growing season. The average total snowfall accumulation is approximately 18 inches.

The following information is for Springfield, IL, which is located approximately 35 miles north of Hillsboro. The average relative humidity is 83 percent in the morning and 63 percent in the afternoon. With the exception of January, the prevailing average wind direction throughout the year is from the south. In January, the average wind direction is from the west-northwest. The average wind speeds are greatest in January, March, April, and November, at 13 miles per hour (mph). The lowest average wind speeds are in July and August, at 8 mph.

B. Topography and Hydrology

The surface topography of the Site is relatively level, with surface elevations ranging from about 600 feet above mean sea level (msl) at the southwest retention pond to about 635 feet above msl in the central portion of the Site. The predominant topographic slope of the Site is southerly. Three surface water ponds exist at the Site: a southwestern storm water retention pond; an engineered storm water retention pond located near the eastern Site property boundary; and a small pond located in the southeastern part of the Site. The southwestern storm water pond receives a large proportion of the Site's storm water runoff. Storm water intermittently discharges westward from this pond to a drainage swale, which in turn discharges to an unnamed intermittent tributary of Middle Fork Shoal Creek. This outfall is permitted with the Illinois Environmental Protection Agency (IEPA) Division of Water Pollution Control as National Pollutant Discharge Elimination System (NPDES) Outfall 001. Middle Fork Shoal Creek Flows southwestward and joins Shoal Creek approximately 6 miles southwest of the Site.

Storm water that originates in most of the manufacturing areas and the easternmost part of the Site enters an engineered storm water retention system located near the eastern property boundary. The storm water retention system includes a small concrete settlement structure and a two-cell, clay-lined retention pond. This system is designed to provide adequate detention time to clarify the water prior to discharge. Storm water generally evaporates from the retention basins or is used as make-up water for the plant's non-contact cooling system. However, periodically, storm water would be discharged to a drainage swale (designated NPDES Outfall 002), which channels the storm water off the Site property to the east. The drainage swale extending from Outfall 002 discharges to Lake Hillsboro, approximately ½-mile east of the Site. Lake Hillsboro is a man-made reservoir, which discharges to Middle Fork Shoal Creek approximately one mile north of the Site.

The southeastern pond is located between two railroad spurs near the entrance to the plant. This pond does not appear to receive storm water runoff and has no inlet or outlet.

In addition to the drainage pathways noted above, storm water that collects in a limited area along the southern Site boundary discharges to a small stream located south of the Site. This stream joins the drainage swale that originates at Outfall 001 just west of the southwest Site property line.

According to the National Wetland Inventory (NWI) Map for Hillsboro, Illinois (U.S. Fish and Wildlife Service, 1988) the only mapped wetlands on the Site property include the southwest retention pond and the small pond located in the southeast part of the Site. These ponds are mapped as "intermittently exposed palustrine wetlands with unconsolidated materials in diked or impounded areas". According to the Federal Emergency Management Agency (FEMA) Flood Hazard Boundary Map for Montgomery County, Illinois (1991), no portions of the Site or the off-Site areas planned for investigation are located within either a 500-year or 100-year flood zone.

According to Illinois State Geological Survey (ISGS) publications, the Site is located within the Central Lowland Physiographic Province of Illinois. Within this province, the Site lies within the Springfield Plain Division of the Till Plains Section. This area is characterized by Pleistocene glacial till and outwash deposits derived from the Illinoian Stage glacial episode.

C. Soils

According to the *Soil Survey of Montgomery County* (USDA Soil Conservation Service, 1969), the soils at the Site belong to five types, generally corresponding to their elevation and proximity to drainage channels. The soil types are described as follows:

-5- ENVIRON

<u>Hickory Series</u>: These are severely eroded soils that exist on 7 to 25 percent slopes at the Site. The Hickory Series consists of deep, well-drained, moderately permeable soils on dissected till plains.

<u>Blair Silt Loam:</u> These are moderately eroded soils that form on 7 to 9 percent slopes. The Blair Series consists of very deep, somewhat poorly drained, moderately slowly permeable soils on dissected till plains. They formed in silty, water-worked sediments, or in sediments and the underlying till that contains a strongly developed paleosol.

Stoy Silt Loam: These are very deep, somewhat poorly drained, slowly permeable soils formed in loess on uplands. Slopes range from 0 to 10 percent.

<u>Hosmer Silt Loam:</u> These are eroded or non-eroded soils that form on 4 to 7 percent slopes. The Hosmer Series consists of very deep, moderately well drained soils formed in Loess on hills.

<u>Cowden-Piasa Complex:</u> At the Site, these form on 0 to 2 percent slopes. The Cowden Series consists of very deep, poorly drained, low permeability soils that formed in Loess on broad upland plains. The Piasa Series consists of very deep, poorly drained, low permeability soils formed in loess and the underlying till on broad, nearly level interfluvial areas on the Illinoian till plain.

D. Geology

According to the map entitled *Thickness of Glacial Drift in Illinois* (ISGS, 1975), the Site is underlain by between 50 and 100 feet of Pleistocene-age unconsolidated glacial deposits. The surface deposits in the area of the Site consist of up to 5 feet of loess, which are wind-blown deposits generally consisting of silt. According to the map entitled *Quaternary Deposits of Illinois* (ISGS, 1979), the site is underlain by the Vandalia Member of the Glasford Formation. This unit consists of hard, compact sandy or silty till. According to maps contained in the document entitled *Potential for Contamination of Shallow Aquifers in Illinois* (ISGS, 1984), the geologic materials underlying the Site are classified as Type E, which is described as "uniform, relatively impermeable silty or clayey till at least 50 feet thick, with no evidence of inter-bedded sand or gravel". This description is verified by monitoring well installation logs prepared by Goodwin & Broms, Inc. (GBI) as part of a ground water investigation conducted at the Site in November 1998. The soil borings for all of the monitoring wells except for G-

107 terminated at 15 feet below grade. The logs indicate that, with the exception of the soil boring for well G-107 which encountered thick deposits of residue materials, clay, silty clay and sandy clay were encountered to a depth of 15 feet below ground surface (bgs) at locations throughout the Site.

According to the Geological Map of Illinois (ISGS, 1967), the glacial deposits are underlain by bedrock consisting of the Pennsylvanian-age Bond Formation. This unit is between 100 and 300 feet thick and predominantly consists of limestone, with some layers of shale and sandstone.

E. Hydrogeology

A shallow ground water contour map (Figure 4) was constructed by ENVIRON using water level measurements made by GBI in December 1998. GBI collected water level measurements from all 13 on-Site wells. As shown on Figure 4, the inferred shallow ground water flow direction generally varies across the Site - southwestward in the southwest part of the Site, to southward and southeastward in the northern and central portions of the Site. Based on the ground surface elevations at the monitoring wells, the inferred pattern of shallow ground water flow generally reflects the Site topography.

Site activities conducted by Philip Services Corporation (Philip) as part of an underground storage tank investigation completed at the Site in 2000¹ included the completion of four slug tests within monitoring wells installed in the southeastern portion of the Site. The slug tests indicated hydraulic conductivities in the shallow water-bearing zone that ranged from 1.11 x 10⁻⁴ centimeters per second (cm/sec) to 8.54 x 10⁻⁵ cm/sec. These measurements are within the ranges of hydraulic conductivity generally reported for both glacial till and loess.

ENVIRON submitted a request to the IEPA for a 1-mile radius search of potential water supply wells and conducted an on-line search of well records maintained by the Illinois Department of Natural Resources (IDNR). The IEPA's Department of Public Water Supply reported that no community water supply wells are located within 2,500 feet of the Site boundaries. Several domestic wells were reported by the Illinois State Water Survey (ISWS) as being located within a one-mile radius of the Site. The well search results, including the IDNR well records and ISWS one-mile radius plot, are included in Attachment A.

In addition, ENVIRON reviewed the results of well searches previously conducted for the Site (Philip, 2000). The ISGS provided Philip with a survey map and well records for several domestic wells located in the general vicinity of the Site. In addition, the

-7- ENVIRON

¹ As documented in a report entitled *Site Classification Completion Report*, dated September 13, 2000 ("Philip, 2000").

ISWS indicated 4 shallow monitoring wells and 3 shallow domestic wells in Section 1 of T8N, R4W, where the Site is located. The information provided by ISGS and ISWS is included in Attachment B. Mr. Robert Kirk, Director of Public Health for Montgomery County was contacted by ENVIRON concerning the potential existence of public or private water wells in the vicinity of the Site. Mr. Kirk indicated that although there are no local ordinances prohibiting the use of private wells, all residents of Hillsboro are provided with public water, which is obtained from Lake Hillsboro and Glen Shoals Lake. ENVIRON confirmed with Mr. David Booher, Water Superintendent for Hillsboro, that the City does not have any public water supply wells.

Finally, ENVIRON conducted a drive-by reconnaissance of properties adjoining the Site. ENVIRON did not observe any water supply wells on these properties².

In addition to information on nearby water supply wells, ENVIRON obtained analytical results for several rounds of surface water samples collected from Lake Hillsboro by IEPA's Division of Public Water Supply between April and October 2001. The samples were collected from the area of the City's potable water intake, which is located near the dam for the reservoir, approximately one mile north of the Site. The samples were analyzed for metal, pesticides, and certain inorganic and physical parameters. The results indicate that no metal or pesticides have exceeded federal primary Maximum Contaminant Limits (MCLs). Manganese concentrations exceeded the secondary MCL for manganese in some of the samples, likely representing background concentrations.

-8-

² A door-to-door survey to obtain information on private wells was not conducted by ENVIRON as part of the PSE, nor was such a survey conducted by Philip as part of its previous wells searches. Such a survey was determined not to be necessary at this time.

IV. SITE HISTORY AND OPERATIONS

A. Site History

The following information concerning the history of the Site is largely summarized from the report entitled CERCLA Expanded Site Inspection Report prepared by the IEPA in 1994, a September 5, 2000 letter prepared by Eagle-Picher responding to an information request received from IEPA, a report entitled Environmental Risk Assessment prepared by Risk Science International in 1982, historical information sources reviewed at the Hillsboro Public Library, and discussions with Eagle Zinc Company personnel. Zinc processing operations began at the Site in 1912, at which time the facility operated as a zinc smelter under the name Lanyon Zinc Company. The smelting products included zinc and sulfuric acid. The Site was purchased by Eagle-Picher Industries in 1919. Eagle-Picher conducted zinc smelting and manufacture of sulfuric acid until approximately 1935. Sometime after 1919 and most likely during the early 1920s, the manufacture of zinc oxide and leaded zinc oxide commenced at the Site. The leaded zinc oxide was manufactured by combining basic lead sulfate (obtained from off-Site sources) with zinc oxide. Additional details on the leaded zinc oxide operation are currently unavailable; however, these activities ceased around 1958. Eagle-Picher continued to manufacture zinc oxide at the Site until November 1980, at which time the Site was purchased by The Sherwin-Williams Company. According to Sherwin-Williams personnel, The Sherwin-Williams Company conducted manufacturing operations for a period of less than one year. In 1984, the facility was sold by The Sherwin-Williams Company to Eagle Zinc Company, a division of T.L. Diamond & Company. Eagle Zinc has predominantly continued manufacturing zinc oxide using the American process employed by Sherwin-Williams and Eagle-Picher.

ENVIRON obtained copies of historical aerial photographs covering the Site area. The following photographs were reviewed, with sources noted: ³

- Montgomery County Natural Resources Conservation Service 1986
- Vista Information Solutions 1973, 1987, and 1998
- National Aerial Resources 1938, 1956 and 1968

In general, the aerial photographs show the progressive development of residences and industry surrounding the Site, as well as the expansion of on-Site facilities, including buildings and the areas of the Site on which operations occurred. Copies of the aerial

-9-

³ Aerial photographs from other sources investigated had limited availability or inappropriate scale.

photographs⁴ are included in Attachment C. The aerial photographs are described as follows:

1938: Significantly fewer buildings existed at the Site in 1938; most notably, the current office building, the zebra building, the Block 2 furnace building, cooling loops and all associated equipment, and several smaller buildings did not exist. However, several buildings existed west and north of Building C, which do not currently exist. Most, if not all, of the northernmost part of the Site appeared to be cropland, and large portions of the area west of the manufacturing plants appeared to have been unused, consisting of open, undeveloped land. Lake Hillsboro existed in its current configuration. A few houses existed immediately west of the Site, but other than the former Hillsboro Glass manufacturing facility, located southeast of the Site, none of the industrial or commercial properties that currently border the Site existed. The areas north and east of the Site consisted solely of farmland. Of particular note, the southwest pond was approximately three times larger than its current size, extending further to the north and east.

1956: In 1956, the configuration of Site buildings generally appeared as it does today. The aforementioned buildings west of Building C had been demolished between 1938 and 1956. The Block 2 furnace building and associated structures had been constructed between 1938 and 1956. Several conical stockpiles existed in the southern portion of the Site, which appeared to consist of raw material feedstock. All other areas of the Site, including the southwest pond and undeveloped northern and western areas, appeared unchanged from the 1938 aerial photograph. Significant development of residential areas west and south of the Site occurred between 1938 and 1956, as well as construction of railroad facilities (roundhouse and other buildings) immediately southeast of the Site.

1968: This aerial photograph appears generally the same as the 1956 photograph, with two exceptions: several small buildings located north of Building C had been demolished; and the southwest pond had been drained to less than one-quarter of its previous size, presumably by creating the outlet now referred to as Outfall 001. According to Eagle Zinc personnel, the pond may have been partially drained during prior to 1968 to limit recreational use of the pond or as a result of public safety concerns. There also had been increased industrial development south and

-10- ENVIRON

⁴ Copies of the aerial photographs obtained from National Aerial Resources were enlarged to show site features.

east of the Site, including expansion of the former Hillsboro Glass manufacturing facility.

1973: In this photograph, the southwest pond appears to contain little or no water. Stockpiling of materials, both feedstock and residuals, is more evident in the southern portion of the Site, immediately west of the manufacturing plant and in the northern parts of the plant.

1986/1987; 1998: Although the locations of material piles differ somewhat, these photographs show the Site as it appears today, including the current configuration of the southwest pond.

B. Description of Historical Operations

Zinc oxide has been manufactured at the Site using both direct and indirect processes. The indirect process reportedly involved the processing of zinc metal in a muffle furnace. The direct process, which continues to be used at the Site (the American process) involves the processing of zinc ores and stockpiled furnace residues in a rotary kiln furnace. While it is likely that Eagle-Picher, Sherwin-Williams and Eagle Zinc all used the direct process, only Eagle-Picher and Sherwin-Williams used the indirect process (muffle furnace). Residual materials historically generated by the manufacturing operations have included, among other things, rotary kiln residue, muffle dross, metallic zinc particles, and refractory bricks from the facility's furnaces. Zinc oxide is used in many applications, including the paint and ceramics industries, agricultural products, rubber products and cosmetics.

As discussed in Section IV.A above, other products historically manufactured at the Site include leaded zinc oxide, metallic zinc, and sulfuric acid. Sulfuric acid was reportedly manufactured at the Site by roasting zinc sulfide to remove the sulfur with the southwest surface water pond used to provide non-contact cooling water. In addition, the facility has produced a fine-grained product that is rich in carbon by screening stockpiled rotary residues using a rotary screen and other methods.

C. General Description of Zinc Oxide Manufacturing Process

The pyrometallurgical process currently used by Eagle Zinc for zinc oxide manufacturing, and which had also been used by Eagle-Picher and Sherwin-Williams, is known as the American process. As currently implemented, this process involves mixing zinc-bearing feedstocks with sized anthracite coal at the mix room. The coal is delivered to the Site by railcar; the zinc ore is delivered to the Site by railcar and truck. The

-11- ENVIRON

furnace mix is fed into a natural gas-fired rotary furnace, 8-foot diameter by 50 foot long, at the Block 2 Furnace Building. The natural gas provides the heat source and the anthracite coal provides a reducing atmosphere to reduce the zinc feedstocks to zinc vapor. The zinc vapor is drawn from the rotary furnace into a refractory brick combustion chamber and combusted to zinc oxide by the addition of ambient air. The zinc oxide, suspended in the vapor stream (products of combustion and air), is drawn into a steel flue and a series of steel cooling loops to cool the zinc oxide and vapor stream before it is collected in a baghouse. The residue left in the rotary furnace is expelled from the rotary furnace into the discharge chamber, quenched in water and hauled to a pad for storage. The zinc oxide collected in the baghouse is conveyed to the refinery and stored in bins before refining. Based on the physical and chemical properties of the zinc oxide, bins of zinc oxide may be blended while being refined. The refining process involves conveying the zinc oxide through a natural gas fired rotary dryer in which the temperature of the zinc oxide is varied to achieve the desired product characteristics. The historic operation of the American process would have been similar.

D. Description of Current Operations

Eagle Zinc currently produces two products: zinc oxide by the American process (described above), and a carbon-rich by-product by a screening process.

The facility screens stockpiled rotary residues using a double rotary screen with ¼-inch and 2-inch screen sizes to produce the fine-grained product that is rich in carbon. This operation is conducted on a concrete pad located immediately west of the zebra building. Large and medium oversize materials created by this process are currently stockpiled to the west of the concrete pad. Eagle Zinc is exploring options for beneficial reuse of this material and is consulting with IEPA on these efforts.

Eagle Zinc has also produced zinc oxide using a Waelz Kiln in the Block 3 Building as part of a pilot project. The Waelz Kiln process feedstock is the furnace residue from Block 2 and stored residue onsite. The Waelz Kiln operates like the Block 2 process where the zinc oxide is collected in a baghouse. The product collected is used as a feed for Block 2. The Waelz Kiln has not been used since October 2000.

In addition, Eagle Zinc formerly conducted a metallic zinc granule process in the zebra building, located in the northern part of the manufacturing plant. Crude zinc granules were conveyed to a Stedman Mill and then screened. The granule product was screened to a desired size fraction. The oversize material (metallic zinc) was collected and shipped off-Site to a different zinc processing facility. The undersized fraction was zinc oxide, which was sold in bulk. This operation was last conducted in September 2001.

-12- ENVIRON

E. Residual Materials

For the purpose of characterizing plant residual materials, residue piles have been categorized as the following types: RR1 (Rotary Residue Type 1); RR2 (Rotary Residue Type 2); RRO (Rotary Residue Oversize); RCO (Rotary Clean Out); CPH (Carbon Plant Hutch); and MP (Miscellaneous Piles). These residue types were described by Eagle Zinc personnel as follows:

RR1: Rotary Residue Type 1 originated from the passing of feedstock through a rotary furnace under the normal American Process. Rotary furnaces 1, 2 and 4 all may have produced this type of residue. The residue is a carbon-bearing material and the non-carbon material is typically smaller than the Rotary Clean Out residue. Much of this material has been processed by screening, resulting in carbon-rich material, which is sold and/or reused on-Site in the process, and oversize materials, which are currently stockpiled pending approval for off-Site beneficial reuse.

RR2: This material came from the Block 3 rotary kiln (now referred to as the Waelz Kiln) prior to 1979 and most likely much earlier. The feedstock that resulted in this rotary residue likely consisted of muffle dross; therefore, this material could differ chemically from RR1 residues.

RCO: Rotary Clean Out residue exhibits, for the most part, the same characteristics as Rotary Residue Type 1. It originates from the formation of a slag ring in a rotary furnace, which is removed with the use of an air hammer. Therefore, it tends to have a larger proportion of irregular shaped particles. Production of this type of residue could have occurred any time a rotary furnace was used. The frequency of furnace clean-out has varied significantly.

RRO: Rotary Residue Oversize material consists of Rotary Residue Type 1 that is passed through a screening process. RRO currently generated by Eagle-Zinc consists of material that is between ¼-inch and 2 inches in size. However, RRO materials historically generated at the Site ranged in size from ¼-inch to significantly larger than 2 inches. RRO material currently generated by Eagle Zinc is staged at a designated location in the northern part of the Site. This is the same location that was historically used to store RRO.

<u>CPH</u>: Carbon Plant Hutch residues were historically produced by a process that passed RR1 residues through a 1/8- or 1/4-inch screen. A majority of the carbon-

-13-

containing material would pass through the screen and the large particles would be rejected. The carbon-rich fraction would then go through a carbon jig, which consisted of a series of two pans. Water was pumped upwards through the pans. The carbon floated at the top and the heavier material was carried along the bottom. It is the heavier material, called "hutch", which makes up the CPH residue piles.

<u>MP</u>: The materials referred to as "miscellaneous piles" for the purpose of sampling may have originated from the historic use of retort or Wetherill furnaces. These piles also appear to contain other debris, such as refractory brick, construction rubble, and pipe fragments.

V. REGULATORY HISTORY

The following information concerning the regulatory history of the Site is largely summarized from the report entitled *CERCLA Expanded Site Inspection Report*. Key events in the operational and regulatory history of the Site are noted in the form of a timeline in Attachment D. The facility was initially listed on the Comprehensive Environmental Response Compensation and Liability Information System (CERCLIS) on June 1, 1981 as a discovery action initiated during Sherwin-Williams' ownership of the Site. Sherwin-Williams reportedly filed U.S. EPA form 8900-1, Notification of Hazardous Waste Site, in accordance with Section 103(c) of CERCLA, which indicated that slag had been disposed on the Site property. A Preliminary Assessment (PA) of the Site was conducted in 1984 by the IEPA pursuant to CERCLA, which culminated in the submission of a PA Report to U.S. EPA Region V. Sampling of residual materials by IEPA in the early 1980s resulted in a determination that the materials were not hazardous waste and the Site was not subject to RCRA permitting.

In addition to the CERCLA activities described above, several sets of surface water samples were collected by the IEPA from the southwest storm water discharge between 1980 and 1982 and analyzed for metals. Detected concentrations of zinc, iron, lead and copper in the surface runoff above applicable state surface water quality standards on one or more occasion resulted in a Notice of Violation (NOV) from the IEPA. This reportedly prompted Sherwin-Williams to remove approximately 18,000 tons of residue materials from 10 acres of the Site.

A CERCLA Expanded Site Inspection was conducted by IEPA on October 26 and 27, 1993, including the collection of 28 environmental samples. The results of the Expanded Site Inspection are summarized in the following section. Based on information provided by IEPA and as reported in the Expanded Site Inspection Report, the USEPA's Chief of Emergency Response for Illinois, Mr. Donald Bruce, determined that the Site did not require a time-critical or non time-critical removal action, and that the Site property does not pose an immediate threat to human health or the environment.

On May 22, 1998, Eagle Zinc entered into an Interim Consent Order with the Illinois Attorney General and IEPA, which contained an interim site plan for: (1) preparation and submittal of a Storm Water Pollution Prevention Plan (SWPPP), (2) sampling of on-site materials, (3) sampling of storm water discharges, (4) development and implementation of a ground water monitoring plan, and (5) disposal of construction and demolition debris.

Pursuant to the Interim Consent Order, a monitoring well installation and ground water sampling program was conducted at the Site by GBI, which included the

installation and sampling of nine shallow monitoring wells. IEPA representatives collected split samples from the monitoring wells. This investigation culminated in the submission of the March 1999 report entitled *Monitoring Well Installation and Ground Water Sampling Interim Report* to the IEPA. Sampling of residual piles and underlying soils was also conducted by GBI pursuant to the Interim Consent Order. The results of this investigation, which also included the collection of split samples by IEPA, were submitted to IEPA in a March 1999 report entitled *Interim Report of Residue Sampling and Analysis*.

Based on the Site's discharges of storm water from two point sources, the occurrence of "regulated industrial activities" at the Site, and the facility's SIC code, the Site was determined to be subject to NPDES storm water permitting requirements as per 40 CFR 122.26 (b)(14)(ii). A NPDES Notice of Intent (NOI) was prepared by Eagle Zinc and submitted to the IEPA. On June 20, 2000, IEPA issued NPDES Permit No. IL0074519. The NPDES permit requires: monthly monitoring of NPDES Outfall 002, preparation/implementation of a SWPPP, and submission of an annual inspection report to IEPA. A SWPPP was prepared for the Site in December 2000. The structural improvements and best management practices specified in the SWPPP included the construction of a new storm water retention system in the northeast area of the Site to allow for settling of runoff prior to discharge to Outfall 002. The storm water retention system, which consists of a two-cell retention basin, was completed in 2001.

The removal of a 500-gallon gasoline UST in April 1998 resulted in the reporting of a Leaking UST (LUST) incident to IEPA, because a limited amount of impacted soil was observed in the tank excavation and a pin-size hole was observed in the tank itself. No free-phase gasoline or ground water was observed in the tank excavation. No contaminated soil was excavated or transported off-Site. The former location of the UST is indicated on Figure 2. The monitoring wells used for the UST investigation (MW-A, MW-B, MW-C/G-106, MW-D and MW-E) are shown on Figure 4.

To address the LUST incident, site classification and assessment activities were performed by GBI and Philip, including: (1) screening of soil samples collected from soil borings using a photoionization detector (PID)⁵, (2) collection of a soil sample for laboratory analysis of benzene, toluene, ethylbenzene and xylenes (BTEX), (3) collection of soil samples for particle size analysis, (4) installation of four new monitoring wells, (5) sampling of five monitoring wells for BTEX compounds⁶, (6) completion of slug tests to estimate hydraulic conductivity, and (7) completion of a well search. Neither the soil

⁶ Pre-existing well G-106 was designated MW-C and sampled as part of the UST investigation.

-16-

⁵ The soil screening included the soil borings for wells MW-A through MW-E, as well as a soil boring completed to a depth of 5 feet below grade located 20 feet west of the former UST.

sample, nor any of the ground water samples collected from the monitoring wells to date have contained detectable concentrations of BTEX compounds. Based on these results and discussions with IEPA, the LUST incident was classified as "low priority" and ground water in the former tank area is being monitored periodically for three years⁷, after which time a no further action proposal is expected to be made, barring any detections of contaminants above applicable ground water standards. The monitoring program continues to be conducted by Philip on behalf of Eagle Zinc Company, and all reports are submitted to IEPA. The ground water monitoring program associated with the former UST is being completed independently from the RI/FS.

-17-

⁷ Quarterly during the first year, semi-annually during the second year, and annually in the third year.

VI. EVALUATION OF EXISTING DATA

Several environmental investigations have been conducted on-Site and in adjacent off-Site areas since the early 1980s. These investigations are summarized in Table 1. The data generated by the previous investigations are summarized below by medium, including soil, sediment, residues, surface/storm water, and ground water. Data summary tables are provided for each medium. The analytical data were compared with: (1) site-specific background data collected during the investigations; and (2) regional background values. Where site-specific background data were available, the "t-Test" was used to determine if a statistically significant difference exists between the media data and background. These comparisons were used in the preliminary identification of potential contaminants of concern (PCOCs) and potential areas of concern (PAOCs).

A. Soil

The 1982 Environmental Risk Assessment report prepared by Risk Science International (RSI) presents the results of soil samples collected at various locations on the Site property in October 1980. RSI's report states that the soil samples did not contain concentrations of metals significantly above background soil samples collected in the Hillsboro area. Concerning the soil data noted in RSI's report, all of which were collected by others prior to RSI's risk assessment, the 1982 report concluded: "much of the lead, cadmium, copper, and zinc, although high in concentrations in the dross, kiln residues and ore spoils, appears to be relatively inert and fixed in these materials." An accurate location map for the soil samples was not available to ENVIRON for review. Therefore, the conclusions made by RSI are discussed herein for informational purposes only, and the soil data collected in 1980 have not been included in the preliminary evaluation of Site soil data discussed below.

The Expanded Site Inspection conducted by IEPA included the collection of 18 soil samples: a background sample and duplicate sample collected from a location in the nearby town of Butler, and 16 samples collected at various off-Site locations. All soil samples were collected from the ground surface (0-4 inches below grade) and analyzed for Target Compound List (TCL) inorganic compounds. The locations of the off-Site soil samples collected in 1993 are shown on Figure 5.

In May 1998, 44 soil samples were collected by GBI at 25 on-Site boring locations. In addition, 6 split samples were collected by IEPA representatives. The boring locations were grouped within four Site areas, which were designated Areas 1 through 4. Between one and three samples were collected from each of the soil borings, which generally extended to the depth at which native clay was encountered. All soil samples were

analyzed for lead and cadmium, with selected soil samples also analyzed for Toxicity Characteristic Leaching Procedure (TCLP) lead and TCLP cadmium. The locations of the soil samples collected by GBI in May 1998 are shown on Figure 6.

The results of the soil samples collected off-Site and on-Site are presented in Tables 2 and 3, respectively. All non-leachate data, both on-Site and off-Site, were compared with Metropolitan Statistical Area (MSA) and non-MSA background values presented in the Illinois Tiered Approach to Corrective Action Objectives (TACO), and off-Site soil data were statistically compared with the results of off-Site background samples collected by IEPA using the t-Test.

Based on these comparisons, no constituent concentrations were determined to be significantly different from site-specific background levels. While arsenic concentrations were determined to be different from site-specific background, the highest detected concentration was only marginally above the average regional background level, as reflected by the non-MSA background value⁷. In addition, arsenic is not known to have been used or released at the Site. As the off-Site soil samples were well distributed around the Site, the available data do not indicate any detectable impacts to off-Site soils through airborne emissions from the Site or other pathways.

For on-Site soil, the lead and cadmium concentrations in each soil area exceeded site area background levels determined by IEPA in 1993, as well as MSA and non-MSA background values. Based on these comparisons, Areas 1 through 4 have been identified as PAOCs for on-Site soil at this time, with lead and cadmium as the principal constituents. As the amount of on-Site soil data is limited, these metals will be considered PCOCs, pending collection of additional data.

B. Sediment

Eight sediment samples were collected by IEPA as part of its October 1993 Expanded Site Inspection. Three of the samples were collected on-Site: sample X-205 from the area of Outfall 001 (drainage point for southwest pond); sample X-206 from the upper reach of the storm water drainage swale that discharges to the southwest pond; and sample X-207 from the drainage swale in the northern part of the Site that discharges at Outfall 002. The remaining samples were collected at off-Site locations in the eastern drainageway (sample X-208) or within the western drainageway (samples X-203 and X-204). Background sample X-201 and its duplicate (X-202) were collected from an unnamed tributary to Middle Fork Shoal Creek, upgradient of the point at which NPDES Outfall 001 discharges to this tributary. All sediment samples were analyzed for the full

-19- ENVIRON

⁷ Montgomery County is listed in TACO as being located within a non-MSA area.

TCL list, including both organic and inorganic compounds. The locations of the sediment samples collected by IEPA in October 1993 are shown on Figure 7.

Table 4 is a compilation of the sediment sampling data. The data were compared with relevant background values. Based on this evaluation, the two major drainageways that receive storm water discharges from the Site have been identified as PAOCs for sediments. The principal constituents identified for sediments at this time include: antimony, arsenic, beryllium, cadmium, lead, nickel, silver, thallium and zinc. As the amount of sediment data is limited, all of these metals will be considered PCOCs, pending collection of additional sediment data in the drainageways.

C. Residues

Two samples of residue piles, designated X-103 and X-105, were collected by IEPA as part of the 1993 Expanded Site Inspection and 68 samples of residue piles were collected by GBI in May 1998, with split samples collected by IEPA. The samples collected by IEPA in 1993 were analyzed for TCL inorganics; the samples collected by GBI in May 1998 were analyzed for lead and cadmium, with selected samples analyzed for TCLP lead and TCLP cadmium. The residue samples collected by GBI represented 15 discrete stockpiles that were categorized as the following types: RRO (Rotary Residue Oversize); RR1 (Rotary Residue Type 1); RR2 (Rotary Residue Type 2); RCO (Rotary Clean Out); CPH (Carbon Plant Hutch); and MP (Miscellaneous Piles).

The stockpiles and locations of all residue samples collected in 1993 and 1998 are shown on Figure 5. The analytical results for the residue samples are compiled in Table 8. The residue data were compared with RCRA maximum concentrations for toxicity. No samples contained TCLP cadmium concentrations above the RCRA limit. In addition, no samples collected from RRO, RCO, or CPH stockpiles contained TCLP lead concentrations above the RCRA limit. At this time, the RR1, RR2 and MP stockpiles have been designated as PAOCs. The principal constituent appears to be TCLP lead. As the amount of data from the residues piles is limited, TCLP lead will be considered a PCOC, pending collection of additional residue data.

As discussed above, the soil data collected by IEPA do not indicate that off-Site soils have been impacted by historical particulate emissions from the Site. Furthermore, based on current and on-going observations made by Eagle Zinc personnel and ENVIRON, the existing residue piles do not appear to be a source of airborne dust emissions. These observations include the relatively large grain size of the materials exposed at the surface of the stockpiles, the consolidated/compacted nature of the older stockpiles, and no observed airborne dust in the areas of the piles during windy

-20- ENVIRON

conditions. Potential impacts resulting from historical airborne emissions will be evaluated through the soil investigations proposed in the RI/FS Work Plan.

D. Surface Water

10 11

Storm water samples were collected from the outlet for the southwest pond (general area of current NPDES Outfall 001) for laboratory analysis of inorganic constituents on four occasions between 1980 and 1982. Data are available for two of these sampling rounds: November 19, 1981, and March 23, 1982.

On June 9, 1998, pursuant to the Interim Consent Order with the IEPA, first flush and composite samples were collected from Outfall 001 by GBI and analyzed for metals and other inorganic parameters, and on June 29/30, 1998, GBI collected first flush and composite samples from Outfall 002 and analyzed the samples for metals and other inorganic parameters. Since that sampling episode, the facility installed a storm water retention basin to capture storm water prior to it being discharged. In addition, since July 18, 2000, the facility has sampled Outfall 002 on a monthly basis as required under the NPDES permit, which regulates the Site's storm water discharges. The analytical parameters for the monthly sampling rounds are total suspended solids (TSS), sulfate, cadmium, and zinc.

The locations of the previous storm water samples, Outfall 001 and Outfall 002, are shown on Figure 9. The analytical results are summarized in Table 6. For screening purposes, the storm water data were compared with Illinois Water Quality Standards: 35 IAC 302 Subpart B (General Water Quality Standards), and 35 IAC 302 Subpart D (Secondary Contact and Indigenous Aquatic Life Standards). It should be noted that these criteria are statewide standards and are not effluent limitations specific to the facility's NPDES permit.

While historical storm water data collected in the vicinity Outfall 001 in 1981 and 1982 exceeded Subpart B standards for iron and zinc and Subpart D standards for iron, zinc and lead, the samples collected at Outfall 001 in June 1998 did not exceed either the Subpart B or Subpart D standards. The June 1998 results for Outfall 001 were subsequently used by IEPA as a basis for determining that storm water monitoring was not required at Outfall 001 as part of the facility's NPDES permit.

For storm water samples collected at Outfall 002, chromium, copper and zinc have exceeded the Subpart B standards; however, only zinc also exceeded the Subpart D standard. Based on these comparisons, surface water in the Site's two major drainageways has been identified as a PAOC. The principal constituents appear to be

-21-

⁸ No monthly samples are collected during periods when storm water is not discharging from Outfall 002.

chromium, copper, lead, zinc, manganese, iron and sulfate. As the amount of surface water data is limited, all of these inorganic constituents will be considered PCOCs, pending collection of additional surface water data in the drainageways.

E. Ground Water

Nil per

In December 1998, GBI collected ground water samples from nine shallow on-Site monitoring wells. The samples were split with IEPA and analyzed for 35 IAC Part 620.410 inorganic and organic parameters. The locations of the monitoring wells are shown on Figure 4.

No 35 IAC 620 organic constituents were detected in any of the ground water samples collected by GBI or the split samples retained by IEPA. Therefore, Table 7 shows the results of the inorganic analyses. For screening purposes, the ground water data were compared to the Illinois Ground Water Protection Act (GPA) (35 IAC 620) standards. Metals, including lead, iron, manganese, cadmium, and zinc, as well as sulfate, exceeded GPA standards (Class I, Class II, or both). The exceedances were limited to downgradient wells G-107 and G-108, both of which are located in the southwestern part of the Site. Based on this evaluation, ground water in the area of wells G-107 and G-108 have been identified as a PAOC at this time. The principal constituents appear to be lead, iron, sulfate, manganese, cadmium and zinc. As the amount of ground water data is limited, all of these inorganic constituents will be considered PCOCs, pending collection of additional ground water data at the Site.

As discussed in Section V, four monitoring wells were installed by GBI in the area of a former 500-gallon gasoline UST that exhibited evidence of leakage. The sampling results, which indicated no detectable BTEX compounds, show that ground water has not been impacted. As these data were not collected to assess environmental conditions on the Site as a whole and were all non-detect, neither the data nor the on-going UST monitoring program is discussed further in this report. Based on their locations and relative spacing, it is not anticipated that the monitoring wells installed for the purpose of evaluating potential impacts from the tank (i.e., MW-A, MW-B, MW-D, and MW-E) will be used during the RI.

-22- ENVIRON

VII. SITE INSPECTION AND ACCESS

On January 16, 2002, ENVIRON conducted a preliminary inspection of the Site and neighboring properties and visited several local governmental offices to obtain information pertinent to the PSE. ENVIRON also interviewed Eagle Zinc personnel concerning information pertinent to the PSE. In addition to the information presented above, the following information was obtained:

- All Site monitoring wells were inspected and were observed to be in good condition.
- With the exception of some limited areas of steep or uneven terrain, ENVIRON does not anticipate significant on-Site access limitations.
- Through the use of tax maps and physical inspection, ENVIRON has identified
 the off-Site properties on which field activities are expected to be conducted
 during the RI.
- ENVIRON conducted an inspection of the undeveloped northern and western portions of the Site property. With the exception of installation and sampling of monitoring wells by GBI in 1998, these portions of the Site have not been subjected to previous phases of environmental investigation. The majority of the undeveloped area north of the manufacturing plant was historically used as farmland. Based on historical aerial photographs, this area does not appear to have been used by the facility for any purpose. Some limited areas in the vicinity of the eastern drainage ditch, which transects this area of the Site, contain surface deposits of plant residues. Several historical residue piles and surface residue deposits exist in the undeveloped western part of the Site. Using aerial photographs and field sketches, the areas covered by these residues are depicted on Figure 8. Based on ENVIRON's visual observations, these materials appear to be of the rotary residue types described above. As indicated in the SOW, supplementary soil, residue and ground water sampling activities will be conducted in the undeveloped northern and western areas of the Site as part of the RI.

Simis.

VIII. SITE CONCEPTUAL MODEL

Based on the evaluation of previous site data, the following affected media and PCOCs have been identified at this time:

On-Site Soil	Sediment	Residues	Ground Water	Surface Water
	Aı	nalytical Fraction	S	
TAL-Metals	TAL-Metals	TCLP-Metals	TAL-Metals	TAL-Metals
Cadmium	Antimony	TCLP-Lead	Cadmium	Chromium
Lead	Arsenic		Lead	Copper
	Beryllium		Manganese	Lead
	Cadmium		Zinc	Manganese
	Lead		Iron	Zinc
	Silver			Iron
	Thallium			
	Zinc			
			Other	Other
		<u> </u>	Inorganics	Inorganics
			Sulfate	Sulfate

Based on the site investigations conducted to date, the PAOCs for on-Site soil, sediment, residues, surface water and ground water are depicted on Figures 10 through 14, respectively. Based on a qualitative evaluation, the following potential on-Site and off-Site exposure routes have been identified:

	On-Site Soil	On-Site Ground Water	Off-Site Ground Water	Off-Site Sediments	Surface Water
Potentially Affected Population	Employee	Construction Worker	Resident	Resident, Ecological Receptors	Resident, Ecological Receptors
Exposure Route(s)	Inhalation, Ingestion, Dermal	Inhalation, Ingestion, Dermal	Incidental Residential Exposure	Secondary Residential Exposure, Potential Ecological Impacts	Secondary Residential Exposure, Potential Ecological Impacts

The Site Conceptual Model will be modified and supplemented as necessary during the course of the RI/FS, as additional data are generated and evaluated.

IX. PREPARATION OF SUPPORT FACILITIES

Equipment needs for field sampling are expected to include a wheel or track mounted excavator, a truck-mounted hollow-stem auger drilling rig, a direct-push sampling apparatus (e.g., Geoprobe rig) mounted on an all-terrain vehicle, and portable equipment, such as a pressure washer, generators, PID, a portable x-ray fluorescence analyzer, pumps, and other tools for sampling. Following mobilization to the Site, a decontamination pad will be constructed for use during all on-Site sampling work. In addition, it is anticipated that indoor Eagle Zinc facilities will be available for sample screening (as required) and for restroom facilities. The facilities required for implementation of the RI will be discussed in further detail in the RI/FS Work Plan.

-25- ENVIRON

TABLES

Table 1:Summary of Historical Site Investigations Page 1 of 1

Dates	Sampler	Locations	Media	No. Samples	Analytical Parameters	On/Off Site	Dunness
Dates	Sampler	Surface Runoff	Media	No. Samples	1 ar arrecters	Oli/Oli Site	Purpose IEPA Stormwater
1000 1000	I CD A		Ct W	Y 71	Marila	O 0.4	
1980-1982	IEPA	Areas	Storm Water	Unknown	Metals	On-Site	Runoff Concerns
				Soil - 19;	Soils-TAL Inorganics;		CERCLA/HRS
]	1	On-Site/Off-Site	Soil, Residuals,	Sediment - 8;	Sediments-Full		Ranking Data
Oct-93	IEPA	Areas	Sediments	Residuals - 2	TCL/TAL List	On-Site/Off-Site	Requirements
					Lead, Cadmium (also selected		
	GBI; IEPA	On-Site Soils;		Soils - 44;	samples for TCLP		Interim Consent Order
May-98	Split	residual piles	Soil, Residuals	Residuals - 68	lead and cadmium)	On-Site	Requirements
	† *				Selected Metals,		
	Į.				Other Inorganics,		
	GBI; IEPA	Outfalls 001 and			Physical		
Jul-98	Split	002 ²	Storm Water	4	Parameters	On-Site	NPDES Permitting
	1				35 IAC Part		
					620.410 Inorganic		
	GBI; IEPA	Site Monitoring			and Organic		Ground Water
Dec-98	Split	Wells	Ground Water	10	Parameters	On-Site	Assessment

¹ As per 1993 IEPA CERCLA Expanded Site Inspection Report and 1982 Environmental Risk Assessment.

GBI - Goodwin & Broms, Inc.

IEPA - Illinois Environmental Protection Agency

²Outfall 002 also sampled monthly pursuant to general storm water permit

Table 2: Historical Sampling Results - Off-Site Soil Page 1 of 3

Date
 Sample

1993	1993	1993	1993	1993	1993	1993
X101-B/G	X102-B/G	X104*	X106	X107	X108	X109

Parameter

Aluminum (mg/kg)
Ar tirnony (mg/kg)
Arsenic (mg/kg)
Barium (mg/kg)
Beryllium (mg/kg)
Cadmium (mg/kg)
Calcium (mg/kg)
Chromium (mg/kg)
Cobalt (mg/kg)
Copper (mg/kg)
Iron (mg/kg)
Lead (mg/kg)
Magnesium (mg/kg)
Manganese (mg/kg)
Mercury (mg/kg)
Nickel (mg/kg)
Potassium (mg/kg)
Selenium (mg/kg)
Silver (mg/kg)
Scd um (mg/kg)
Thallium (mg/kg)
Vanadium (mg/kg)
Zinc (mg/kg)

12400	Τ	10000	T	6880		13000	T	13000	Γ	11500		10200	T
8.9	J	9.2	J	10.6	J	9.4	J	10.5	J	13	J	9.3	J
5.8		5.7		6.6		6.2		8.7		13.4		4.6	
230		265		181		224		124		267		130	
0.8	В	0.81	В	0.49	В	0.63	В	0.72	В	1	В	0.6	В
				3.2		0.89	В	3.5		11.3		0.71	В
10600		9880		598	В	11600		5360		5430		2580	
16.2		14,4		10.3		15.1		16.1		23.4		13.4	T
4.1	В	6.5	В	13.7		11.1		5.6	В	14.8		6.9	В
20	J	19.7	J	30.6	7	24.7	J	36.4	J	104		15.3	
14700		14400		11500		15400		14900		33900		12600	
148		236		61		28.5		105		388		47	
2370		2090		1040	В	2150		2090		1630		1530	
434		686		1180		922		600		1670		660	
0.17		0.18						0.16		0.16		0.11	В
13.5		11.5		20		14		15.9		35.1		11	
1890		1600		491	J	1060	J	1160	J			1650	
		1.3	J	0.27	J					0.84	J	0.31	J
					<u> </u>								
106	В	87.9	В	47.5	В	37.4	В	71.8	В	178	В	65.7	В
0.33	В	0.34	J	1.2	J	0.26	J	0.35	J	1.4	J	0.28	J
28.5		27.1		27.5		28.5	\coprod	27.3		37.7		24.7	
136		138		4770		1490		2480		2280		360	

В	The reported value is less than the CRDL but greater than the instrument detection limit.
	Estimated value. Used in data validation when the quality control data indicate that a value may
J	not be accurate.
	Not Detected
mg/kg	milligrams per kilograms

^{*}While technically located on-site sample is grouped with other 1993 off-site samples and hence had been compared to more stringent residential values. Source: 1993 CERCLA Expanded Site Inspection Report

Table 2: Historical Sampling Results - Off-Site Soil
Page 2 of 3

ļ	Dat	6
l	Sampl	e

1993	1993	1993	1993	1993	1993	1993
X110*	X111	X112	X113	X114	X115	X116

Parameter

Aluminum (mg/kg)
Antimony (mg/kg)
Arsenic (mg/kg)
Barium (mg/kg)
Beryllium (mg/kg)
Cadmium (mg/kg)
Calcium (mg/kg)
Chromium (rng/kg)
Cobalt (mg/kg)
Copper (mg/kg)
Iron (mg/kg)
Lead (mg/kg)
Magnesium (mg/kg)
Manganese (mç/kg)
Mercury (mg/kg)
Nickel (mg/kg)
Potassium (mg/kg)
Selenium (mg/kg)
Silver (mg/kg)
Sodium (mg/kg)
Thallium (mg/kg)
Vanadium (mg/kg)
Zinc (mg/kg)
· -

15000	<u> </u>	13500	T	9950	Т	16600	T	9750	T^-	14800		12500	T
7.9	J	9	J	10.2	J	7.8	J	8.4	J	11.1	J	9.9	J
13.6		8.5		6.2		5.6		11.9		10.5		7.1	1
150		193		233		116		183		181		227	1
0.78	В	0.94	В	0.85	В	0.85	В	1		0.8	В	0.93	В
2		1.6		2.8		0.68	В	2.9		1.48		2.3	
3450		8380		2800		5940		4230		4970		8430	1
20.7		20.2		14.8		21.7		15.9		19.4		18.9	\mathbf{I}^{-}
8.5	В	7.8	В	11.3	В	10.6		5.8	В	7	В	9.8	В
22.5		33.8		15.9		22.5		28.3	J	27.8	J	25.5	J
20700		19300		13900		20400		28600		19700		18900	
87.6		70.8		70.1		75.1		137		76.2		147	
2500		1950		17.6		4870		1130		2030		2020	
563		491		2070		568		314		538		851	
		0.11	В	0.11	В					0.42		0.24	
15.9		16.5		22.9		18.6		14.4		10.9		16.5	
1980		1920		1970		2400		1040		1470		1750	
0.49	J	0.42	J	0.39	J	0.27	J	0.76	J	0.52	J	0.53	J
										1.2			
62.8	В	120	В	52.4	В	45.8		293	В	61.5	В	89.9	В
		0.25	J	0.28	J	0.27	J	0.71	J	0.57	J	0.53	J
38.7		34.2		28.2		33.7		29.7		34.8		35.1	
606		488		489		451		1580		638		998	

В	The reported value is less than the CRDL but greater than the instrument detection limit.
	Estimated value. Used in data validation when the quality control data indicate that a value may not be accurate.
	
	Not Detected
mg/kg	milligrams per kilograms

^{*}While technically located on-site sample is grouped with other 1993 off-site samples and hence had been compared to more stringent residential values. Source: 1993 CERCLA Expanded Site Inspection Report

Table 2: Historical Sampling Results - Off-Site Soil Page 3 of 3

Date
Sample

1993	1993	1993	1993
X117	X118	X119	X120

Parameter

Aluminum (mg/kg)
Antimony (mg/kg)
Arsenic (mg/kg)
Barium (mg/kg)
Beryllium (mg/kg)
Cadmium (mg/kg)
Calcium (mg/kg)
Chromium (mg/kg)
Cobalt (mg/kg)
Copper (mg/kg)
fron (mg/kg)
Lead (mg/kg)
Magnesium (mg/kg)
Manganese (mg/kg)
Mercury (mg/kg)
Nickel (mg/kg)
Potassium (mg/kg)
Selenium (mg/kg)
Silver (mg/kg)
Sodium (mg/kg)
Thallium (mg/kg)
Vanadium (mg/kg)
Zinc (mg/kg)

				, 	,		,
13800	_	1410	 	9390		16300	<u>L</u> .
14.5	J	10.9	J	8.3	J	8	J
8.5		5.9		6.7		10.7	
222		106		196		155	
1.7		0.73	В	0.6	В	0.95	
4.8		-		2.8			
19300		1720		12100		2870	
17.3		18.5		13.7		20.4	
10.6	В	11.1	В	14.9		7.4	В
57.2	7	15.9	J	17.5	J	17.2	J
21100		18200		14100		22900	
186		30.4		51.9		32.7	
2140		2120		1790		2870	
995		795		1520		889	
0.14	В			0.32			
27.5		12.8		14.8		16.9	
1460	J	1210	٦	1670		1490	
0.35	J	0.27	J	0.55	J	0.38	J
1020	В					27.7	В
0.35	J	0.27	J	0.5	J	0.25	J
34.3		34.5	В	26.7		39	
7420		354		1570		371	

В	The reported value is less than the CRDL but greater than the instrument detection limit.
J	Estimated value. Used in data validation when the quality control data indicate that a value may
	Not Detected
mg/kg	milligrams per kilograms

^{*}While technically located on-site sample is grouped with other 1993 off-site samples and hence had been compared to more stringent residential values. Source: 1993 CERCLA Expanded Site Inspection Report

Table 3: Historical Sampling Results - On-Site Soil Page 1 of 2

				,						
Date	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98
Sample ID	Area 1 - 1S	X201	Area 1 - 1B	Area 1 - 108-8	Area 1 - 2S	Area 1 - 2B	Area 1 - 3S	Area 1 - 3B	X203	Area 1 - 4S
Parameter										
Lead (T) rng/kg	4342	2700	511	2330	4330	15.3	4772	3151	6300	4423
Cadmium (T) rng/kg	16.3	35	9.5	NA	16.8	6.6	30.5	20.8	21	21.5
Lead (TCLP) rng/L	8	3.7	NA	3.37	14.4	NA	23.4	31	29.6	36.3
Cadmium (TCLP) mg/L	0.193	0.17	NA	NA	NA	NA	NA	0.164	0.18	NA
Date	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	_May-98
Sample ID	Area 1 - 4B	_X205	Area 1 - 5S	Area 1 - 5B	X206_	Area 2 - 1S	Area 2 - 2S	Area 2 - 2D	Area 2 - 28	Area 2 - 3S
Parameter										
			,							
Lead (T) mg/kg	1385	4500	1305	1745	2500	1900	2583	2318	552	378
Cadmium (T) mg/kg	15.7	30	7.7	14.5	27	31.2	11.7	45.4	84.1	9.6
Lead (TC_P) mg/L	32	32.4	4.3	5.1	3.8	5.98	2.5	2.96	NA	NA
Cadmium (TCLP) mg/L	0.202	0.16	NA	0.219	0.19	NA	0.149	NA	NA	NA NA
5.43		14- 00		1400	14- 00]	44	14- 00- (- 14 00 T	M= 00	14-11-00
Date	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98
Sample ID	Area 2 - 3B	Area 2 - 45	Area 2 - 4B	Area 3 - 1S	Area 3 - 25	Area 3 - 35	Area 3 - 45	Area 3 - 4B	Area 3 - 5S	X212
Parameter										
(T)		200	450	CCO	42.0	438		40.6	7.1	18
Lead (T) mg/kg	9.2	328	158	650	13.8	15.9	4.6	48.6 7.7	8.8	NA NA
Cadmium (T) mg/kg	2.5 NA	6.5	9.2	22.1	8.8	NA NA	3.3 NA		0.8	NA NA
Lead (TCLP) ng/L		NA	NA NA	0.04 NA	NA NA	NA NA		NA NA	0.064	0.015
Cadmium (TCLP) mg/L	NA	NA	NA	NA I	NA	IVA	NA	NA	0.064	0.015
		The re-enter	Luntin in Inna	than the CRDL	hut granter t	han the instri	mont detecti	on limit		
	В	ne reported	value is less	data validation	but greater t	liby control de	to indicate th	on min.	ay not be acco	urate
				uata validation	when the das	anty Control da	na muicate ti	iai a value Illa	ay not be acci	uiate.
		Not Analyzed	·							
	1 - \-/	Total		ables Description						
				ching Procedur	<u>e</u>					
		nilligrams pe								
	mg/l [r	nilligrams pe	erliter							

Note: "200 Series" samp e identification numbers also used for unrelated sediment samples collected by IEPA in 1993.

Source: 1993 CERCLA Expanded Site Inspection Report 1998 GBI Sampling Event and IEPA Spilt Samples

Table 3: Historical Sampling Results - On-Site Soil Page 2 of 2

Date	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98
Sample ID	Area 3 - 6S	Area 3 - 7S	Area 3 - 7B	Area 4 - 1S	Area 4 - 2S	Area 4 - 3S	Area 4 - 3B	Area 4 - 4S	Area 4 - 4B	Area 4 - 55
Parameter										
Lead (T) mg/kg	887	1260	47.1	5075	267	1.2	20.6	0.4	30.3	8.6
Cadmium () mg/kg	485	27.5	69.6	83.4	22.7	8.8	5	4.3	15.9	3.2
Lead (TCLF) mg/L	0.56	0.54	NA	13.6	NA	NA	0.1	NA	NA	NA
Cadmium (TCLP) mg/L	NA	NA	NA	NA	NA	NA	0.074	NA	NA	NA
<u></u>										_
Date	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98	May-98
Sample ID		Area 4 - 6S	X217						Area 4 - 9D	
		المتقدين المتقديا				التــــــــــــــــــــــــــــــــــــ			<u> </u>	
Parameter										
				,						
Lead (T) mg/kg	17.1	8137	9800	6273	30	160	35.4	789	177	148
Cadmium (T) mg/kg	17.9	53	88	45	24.6	15	24.6	17.9	9.1	6.3
Lead (TCLP) mg/L	NA	4.73	6.7	5.25	NA NA	NA_	0.305	1.48	NA NA	NA_
Cadmium (TCLP) mg/L	NA	0.679	0.001	0.487	NA	NA	0.244	NA	NA	NA
	В	The reported								
	J	Estimated va		data validati	on when the	quality contro	l data indicat	e that a value	may not be	
	NA NA	Not Analyzed	<u> </u>							
	(T)	Total								
	(TCLP)	Toxicity Char	acteristic Lea	aching Proce	dure					
	mg/kg	milligrams pe	er kilograms							

mg/l

milligrams per liter

Table 4: Historical Sampling Results - Sediment Page 1 of 3

								
Date	1993	1993	1993	1993	1993	1993	1993	1993
Sample	X201-B/G	X202 (X201 Dup)	X203	X204	X205	X206	X207	X208
						·		

Volatiles (ug/kg)

Parameter

Methylene Chloride
Acetone
2-Butar one (MEK)
1,1,1-Trichloroethane
Toluene

								-		160	J			T}
11	J	22		12	J			37	U	78	J			
		4	٦	6	7			20	J	48	J			
						27	J	9	J	290	J		8	JJ
		-				7		-		36	J			$\prod 1$

Semi-volatiles (ug/kg)

senii-volatiles (ug/kg)
2-Methylnaphthalene
Phenanthrene Phenanthrene
Anthracene
Carbazole
Fluoranthene
Pyrene
Benzo(a)anthracene
Chrysene
bis(2-ethylnexy)phthalate
Benzo(bifluoranthene
Benzo(killuoranthene
Benzo(a)pyrene

	- 1		TT		TT	100	TIT	1		7-7		T
		280	J	1900			T					7-
				320	J			-		T		
				290	J		\perp					7
		520	J	1700	I_{-}		ΓT	_	130	J		\mathbf{I}^{-}
		520	J	1600	T - T				140	J	<u></u> -	
		230	J	850					100	J		T
		310	J	670	J				120	J		
		660								T		
		480	J		T				140	J		7
				1200			T			T		7
	7	230	J	810	T							T

PCBs (ug/kg) Aroclor-1254 Aroclor-1260

_						 	 	 	 	 	
Γ					250	120				24	J
Γ	17	7	9.3	IJ	110	100				1	

В	Analyte was found in the associated blank as well as in the sample.
J	Estimated value.
	Not Detected
ug/kg	micrograms per kilograms

Table 4: Historical Sampling Results - Sediment Page 2 of 3

Date
Sample

1993	1993	1993	1993	1993	1993	1993	1993
X201-B/G	X202 (X201 Dup)	X203	X204	X205	X206	X207	X208

Inorganics (mg/kg) Aluminum Antimo iy Arsenic Barium Beryllium Cadmium Calciu in Chromium Coba t Copper Iron Leac Magnesium Manganese Mercury Nickel Selenium Silver Sodium Thallium	Parameter
Antimony Arsenic Barium Beryllium Cadmium Calcium Chromium Cobait Copper Iron Leac Magnesium Manganese Vercury Nickel Selenium Silver Sodium Thallium	Inorganics (mg/kg)
Arsenic Barium Beryllium Cadmium Calcium Calcium Chromium Cobat Copper Iron Leac Magnesium Manganese Wercury Nickel Selemum Silver Sodium Thallium	
Barium Beryllium Cadmium Calcium Calcium Chromium Coba t Copper Iron Leac Magnesium Manganese Mercury Nickel Selenium Silver Sodium Thallium	Antimony
Beryllium Cadmitim Calciu n Chromitim Coba t Copper Iron Leac Magnesium Manganese Mercury Nickel Selenium Silver Sodiu n Thallium	Arsenic
Cadmitim Calciu n Chromium Coba t Copper Iron Leac Magnesium Manganese Wercury Nickel Selenium Silver Sodiu n Thallium	Barium
Calcium Chromium Cobalt Copper Iron Leac Magnesium Manganese Wercury Nickel Selenium Silver Sodium Thallium	Beryllium
Chromium Coba t Copper Iron Leac Magnesium Manganese Vercury Nickel Selenium Silver Sodium Thallium	Cadmium
Coba t Copper Iron Leac Magnesium Manganese Vercury Nickel Selenium Silver Sodium Thallium	Calciu n
Copper Iron Leac Magnesium Manganese Vercury Nickel Selenium Silver Sodium Thallium	
Iron Leac Magnesium Manganese Vercury Nickel Selentim Silver Sodium Thallium	
Iron Leac Magnesium Manganese Vercury Nickel Selentim Silver Sodium Thallium	Соррег
Magnesium Manganese Mercury Nickel Selenium Silver Sodium Thallium	
Manganese Mercury Nickel Selenium Silver Sodium Thallium	
Manganese Mercury Nickel Selenium Silver Sodium Thallium	Magnesium
Mercury Nickel Selenium Silver Sodium Thallium	
Selenium Silver Sodium Thallium	
Silver Sodium Thallium	Nickel
Sodiu n Thallium	Selenium
Thallium	
	Sodium
	Thallium
Vanadium	Vanadium

Zinc

CC20	1	6200	_	7070		44000		0000	~-	40000		40700	_		т
6630		6390	نبب	7370	ــــــــــــــــــــــــــــــــــــــ	14900	↓	8360	↓	16300	↓	10700	1	9810	
9	J	10.4	j	10.3	IJ	17.4	J	9.3	<u> </u>	62.7	J	10.7	J	10.8	11
4.5	l	4.3		_6.4		10.9		2.9	I	19.4		6		8	Ι
79.5		70.4		99.9		97.4		89.6	T	383		167		92.5	T
0.4	В	0.4	В	0.5	В	0.6	В	0.5	В	1.5	B	0.7	В	0.6	В
0.7	В	. 1		8.6		7.4		1.8	П	523		11.1		19.6	Ţ
6360_		5520		20300		12000		4660	Π	6260		1510		3020	T
9.9		9.9		12,1		13.2		11		28.6		14.6		13.7	T
6.1	В	4.9	В	6	В	8.1	В	4.5	В	353		10.8	В	4.7	<u> </u>
11.9_		11.2		37.9		41.9		9	1	1420		20.8		52.2	
10100		9120		12400		14300	,	10900	T	82400		14900		14500	T
46.4		35		101		72.5		10.2		932		76		125	T
2760		2390	\top	3330		2960		2620		4970		1500		1930	T
501		384		722		451		85.9		3500		1470		461	
				0.2	П	0.1	В			0.7	П			0.3	T
9.2	В	8.7	В	11.5		14.7	В	12.6	1	583		11.9		12.7	Ţ
0.3	J	0.3	J	0.3	J	0.4	J	0.3	J	4.1		0.3	J	0.4	J
0.2										14.1					T
73.3	В	79.5	В	132	В	150	В	84.7	В	470	В	82	В	110	В
0.3	J					0.4	J	0.3	J	3.8	J	0.3	J	0.4	J
17.9	1 - 1	17.4	\neg	19		26.3		20.8	$\Gamma \exists$	52.9		41.2		27.2	
326		291		2200		3040		5690		156000		2410		3280	

В	Analyte was found in the associated blank as well as in the sample.
J	Estimated value.
	Not Detected
ug/kg	milligrams per kilograms

Source: 1993 CERCLA Expanded Site Inspection Report

Table 4: Historical Sampling Results - Sediment Page 3 of 3

Date	
Sample	

1993	1993	1993	1993_	1993	1993	1993	1993
X201-B/G	X202 (X201 Dup)	X203	X204	X205	X206	X207	X208

Parameter Pesticides (ug/kg)

alpha-BHC
beta-BHC
gamma-BHC (Lindane)
Aldrin
Heptachlor epoxide
Diedrin
4,4'-DDE
Endrin
Endosulfan II
4,4'-DCID
4,4'-D[)T
Methoyxy'clor (Mariate)
Endrin Ketone
alpha-Chlorodane
gamma-Chlorodane
Toxaphene

	,										_				
L	1_1		1_1	-			<u> </u>	<u> </u>		1.5	J		<u>L</u> _	<u> </u>	L .
		-					Ι			1	J				Γ
		-								1.1	J				TT.
]_]			4.4					I	~]_		Γ^{-}
-]]	0.2	J			1.3	J			4.7	J				
2.3]]]	2.6	J	16		12				10	J	-	Ţ	1.3	J
		0.4	LJ							0.7	J		Ι		
0.3	J	0.9	J	18		12		2.4	J		Γ		Ι.	2.8	J
										~				3.6	J
0.4	J	0.9	J	7.5		6	J			1.8	J			5.1	J
3.7	J	0.4	J	11		15				4.8	7	1			
					_					13	_			-	
		0.5	J					1.6	J			-			
2	J	3.1		16		7				1.7	J			0.6	J
2	J	2.5		15		7.4				3	J			0.7	J
		110	J					-						320	P

В	Analyte was found in the associated blank as well as in the sample.
J	Estimated value.
	Not Detected
ug/kg	micrograms per kilograms

Table 5: Historical Sampling Results - Residues Page 1 of 4

Date
Sample ID

1993	1993
X103	X105

Parameter

Lead (T) mg/kg	· [
Cadrnium (T) mg/kg	Г
Lead (TCLP) mg/L	
Cadrnium (TCLP) mg/L	Γ
Aluminum (mg/kg)	
Antimony (rng/kg)	
Arsenic (mg/kg)	
Barium (mg/kg)	
Bery lium (mg/kg)	L
Calc um (mg/kg)	
Chrcmium (mg/kg)	L
Cobalt (mg/kg)	
Copper (mg/kg)	L
Iron (mg/kg)	
Magnesium (mg/kg)	L
Manganese (mg/kg)	L
Mercury (mg/kg)	_
Nickel (mg/kg)	_
Potassium (mg/kg)	_
Selenium (mg/kg)	L
Silver (mg/kg)	\perp
Sodium (mg/kg)	_
Thallium (mg/kg)	L
Vanadium (mg/kg)	\perp
Zinc (mg/kg)	(_

	1040	В
	3.2	
]	NA	
	NA	
	7430	
J	11.4	J
	86.3	
	379	
В	0.83	В
	1930	
	22.6	
В	20.1	
J	911	J
	104000	
	178	
		J
J		
]
		В
J		J
J	24722	,
	В	3.2 NA NA 7430 J 11.4 86.3 379 B 0.83 1930 22.6 B 20.1 J 911 104000 1630 178 55.9 B 300 J 1.3 6.3 B 39.6

В	The reported value is less than the CRDL but greater than the instrument detection limit.
	Estimated value. Used in data validation when the quality control data indicate that a value may not be
J	accurate.
NA	Not Analyzed
	Not Detected
mg/l	milligrams per liter
mg/kg	milligrams per kilogram

Table 5: Historical Sampling Results - Residues Page 2 of 4

	·		·							·	
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
Sample ID	RR1-P1-1S	RR1-P1-1B	X202	RR1-P2-1S	RR1-P2-1B	RR1-P3-1S	X204	RR1-P3-1M	RR1-P3-1B	RR1-P4-1S	RR1-P4-1M
	1										
Parameter											
Lead (T) mg/kg	9970	2241	3000	61.8	986	4339	4000	15000	5292	40	423
Cadmium (T) mg/kg	19.6	15	44	11.8	11.9	30.7	29	14.5	35.4	6.8	8.1
Lead (TCLP) mg/L	123	NA	NA	NA	7.11	24.7	21.3	NA	NA	NA	NA
Cadmium (TCLP) mg/L	0.204	NA	NA	NA	0.123	0.27	0.24	NA	NA	NA	NA
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
Sample ID	RR1-P4-1B	RR1-P4-1B2	X209	RR1-P5-1S	RR1-P5-1M	RR1-P5-1B	RR1-P5-2S	RR1-P5-2M	RR1-P5-2B	RR1-P5-2D	RR1-P5-3S
											
Parameter											
Lead (T) mg/kg	55	2644	3100	23.2	15	4.3	20.8	31.7	5.8	8.2	124
Cadmium (T) mg/kg	6.54	66.7	120	5	1.5	1.4	1.8_	5	2.7	1.2	7.5
Lead (TCLP) mg/L	NA	14.8	16.7	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium (TCLP) mg/L	NA	0.8	0.99	NA	NA NA	NA NA	NA	NA NA	NA	NA	NA
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
Sample ID	R1-P5-3M	RR1-P5-3B	RR1-P5-4S	RR1-P5-4M	RR1-P5-4B	RR1-P6-1S	RR1-P6-1M	RR1-P6-1B	RR1-P7-1S	RR1-P7-1M	RR1-P7-1B
Do											
Parameter											
Lead (T) mg/kg	65.4	153	0.9	2.9	5	5012	2338	3059	16.5	40.7	49.3
Cadmium (T) mg/kg	3.89	8.5	0.1	11.1	12.3	19.3	19.7	25	1.2	5.7	3.6
Lead (TCLP) mg/L	0.2	NA	NA	NA	NA _	NA	8.61	NA	NA	NA	NA
Cadmium (TCLP) mg/L	0.01	NA	NA	NA NA	NA	NA	0.273	NA	NA	NA	NA
											
NA	Not Analyzed										<u>,,, </u>
mg/l	milligrams pe	r liter									
mg/kg	milligrams pe		<u> </u>				·				
L	g. a po										


Table 5: Historical Sampling Results - Residues Page 3 of 4

		·									
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
Sample ID	RR1-P7-2S	RR1-P7-2M	RR1-P7-2B	RR1-P7-3S	RR1-P7-3M	RR1-P7-3D	RR1-P7-3B	RR1-P7-4S	RR1-P7-4M	RR1-P7-4B	X210
	1						-			- · · · · · · · · · · · · · · · · · · ·	
<u>Parameter</u>	J										
Leac (T) mg/kg	24	6.7	11.6	25	31.4	25.9	20	85	26.9	41.4	46
Cadmium (T) mg/kg	4	1.8	5.6	3.9	1.8	0.5	5	7.1	3.8	6.8	3.8
Lead (TCLP) mg/L	NA	0.203	NA	NA	NA	NA	NA	NA	NA	0.255	0.011
Cadmium (TCLP) mg/L	NA	0.055	NA	NA	NA	NA	NA	NA	NA	0.019	0.021
											<u> </u>
Date	1998	1998	4000	4000	4000	4000	4000	4000	4000	4000	4000
Sample ID			1998 MP1-1S	1998 MP1-1B	1998 RCO-P1-1S	1998 X207	1998 BCO B1 1B	1998	1998 RCO-P2-1M	1998 X208	1998 RCO-P2-1B
Sample ID	17/1-10-13	KK1-F0-1B	WF1-13	MP I- IB	KCU-P1-13	A201	KCO-P1-1B	RCU-F2-15	IKCO-P2- IM		RCU-P2-1B
Parameter]										
Lead (T) mg/kg	8.8	45	48695	50290	1.43	49	12.5	120	22.9	36	54.6
Cadmium (T) mg/kg	88	6.1	15.8	24.2	0.61	NA	0.4	5.8	1.94	3.3	6.5
Lead (TCLP) mg/L	NA	NA	255	288	0.41	0.012	NA	NA	0.22	0.007	NA
Cadmium (TCLP) mg/L	NA	0.028	NA	0.22	0.027	0.044	NA	NA	0.038	0.052	NA
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
Sample ID	RCO-P3-1M	RCO-P4-1M	CPH-P1-1S	CPH-P1-1B	CPH-P2-1S	CPH-P2-1B		RF:0-P1-1S	RRO-P1-1M	RRO-P1-1B	RRO-P1-2S
Parameter											
	· · · · · · · · · · · · · · · · · · ·					· · · · · · · · · · · · · · · · · · ·			, 		
Lead (T) mg/kg	2.8	47.9	637	198	65	35.4	77	36.8	44.3	37.2	84.8
Cadmium (T) mg/kg	1.1	10.8	15	13.7	14.2	10	6.3	5	4.3	5.6	3.5
Lead (TCLP) mg/L	NA	NA NA	1.51	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA	NA NA
Cadmium (TCLP) mg/L	NA	NA	0.071	NA	NA	NA	NA	NA NA	NA NA	NA	NA
					 _						
NA	Not Analyzed	i									
	milligrams pe										
mg/kg	milligrams pe	r kilogram									

Table 5: Historical Sampling Results - Residues Page 4 of 4

Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998
		 							 			
Sample ID	IRRO-P1-2M	IRCO-P3-1M	IRCO-P4-1M	CPH-P1-1S	CPH-P1-1B	CPH-P2-1S	CPH-P2-1B	X211	RRO-P1-1S	RRO-P1-1M	RRO-P1-1B	RRO-P1-2S
Parameter	1											
	j											
Lead (T) mg/kg	272	2.8	47.9	637	198	65	35.4	77	36.8	44.3	37.2	84.8
Cadmium (") mg/kg	3.6	1.1	10.8	15	13.7	14.2	10	6.3	5	4.3	5.6	3.5
Lead (TC:LF') mg/L	0.166	NA	NA	1.51	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium (TCLP) mg/L	NA	_ NA	NA NA	0.071	NA	NA	NA	0.015	NA	NA	NA	NA
Date	4000	4000	1000	4000	1000	4000	4000	4000	4000	4600	4000	4000
		1998	1998	1998 RRO-P1-3M	1998	1998 X218	1998	1998	1998	1998	1998	1998
Sample ID	[FRO-P 1-2M	[KKU-P1-2B	1 KKO-P1-38	RRO-P1-3M	1 KKU-P 1-3B	1 7218	KKZ-P 1-15	RRZ-P1-IM	RR2-P1-1B	X216	RRZ-P1-25	RR2-P1-2M
Parameter	ì											
I didiliete:	1											
Lead (T) mg/kg	272	1292	80	842	1696	670	2722	2372	3385	4600	13797	456
Cadmiurri (T) mg/kg	3.6	8.4	16.7	6.7	6.1	6.1	7.3	9.2	5	50	5.8	1.5
Lead (TCLP) mg/L	0.166	0.081	NA NA	NA	0.158	0.084	4.18	5.3	7.11	8.5	16.9	2.74
Cadmium (TCLP) mg/L	NA	0.085	NA	NA	0.028	0.035	0.114	0.069	0.039	0.038	0.057	0 .016
				_								
	4000	1 4000	4000	4000	4000	4000	4000	1000	1000	1000	4000	
Date	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	1998	
Sample ID	X213	RR2-P1-2B	RR2-P1-3S	RR2-P1-3M	RR2-P1-3B	X214	RR2-P1-3D	RR2-P1-45	RR2-P1-4M	X215	RR2-P1-4B	
Danamatan												
Parameter												
Lead (T) mg/kg	860	3186	1589	4362	690	160	274	3147	2781	3300	14298	
Cadmium (T) mg/kg	3	3.6	3.6	7.7	4.2	11	10.4	9.1	2	5.5	46.5	
Lead (TCLP) mg/L	2.6	1.94	5.63	10.6	1.21	0.12	0.29	3.84	5.71	6.7	2.33	
Cadmium (TCLP) mg/L	0.02	0.031	0.016	0.094	0.062	0.11	0.132	0.133	0.046	0.042	0.514	
		· — - — - — ·										
NA NA	Not Analyzed	<u> </u>										
mg/l	milligrams pe	r liter									Ì	
	milligrams pe											
	рс											

Table 6: Historical Sampling Results - Storm Water Page 1 of 2



	0C2	002	002	002	002	002	002	002	002	002	002	002	002	002
1	First Flush	COMP	First Flush	COMP										
Į	6/30/1998	6/30/1998	6/29/1998	6/29/1998	7/18/2000	8/17/2000	9/12/2000	10/4/2000	11/16/2000	12/11/2000	2/9/2001	3/15/2001	5/5/2001	6/15/2001

<u>Parameters</u>

Flq
Fluoride (mg/L)
Sulfate (mg/L)
Ammonia (as N) (mg/L)
Phosphorus-P (T) (mg/L)
BOD5 (mg/L)
FOG (T)
Mercury (T) (mg/L)
Calcium T) (mg/L)
Sodium (T) (mg/L)
Sodium (T) (mg/L) Aluminum (T) (mg/L)
Boron (Ti (mg/L)
Cadmium (T) (mg/L)
Copper (T) (mg/L)
Iron () (ing/L)
Mangenese (T) (mg/L)
Silver T) (mg/L)
Vanadium (T) (mg/L)
Hardriess (mg/L)
(ROE) TDS (mg/L)
Chloride (T) (mg/L)
Nitrate Nitrite (N Total) (mg/L)
Cyanide T) (mg/L)
TSS (mg/L)
Antimony (mg/L)
Arseric (T) (mg/L)
Selenium (T) (mg/L)
Magnesium (T) (mg/L)
Potassium (T) (mg/L)
Barium (T) (mg/L)
Elerylliumi (T) (mg/L)
Chroinium (T) (mg/L) Coba : (T) (mg/L)
Coba ! (T) (mg/L)
Lead (T) (mg/L)
Nickel (T) (mg/L)
Strontiurn (T) (mg/L)
Thall um (mg/L)
Thall um (mg/L) Zinc T) (mg/L)
COD (mg/L)
TDS (Conductivity)
Chromit m Hexavalent) (mg/t.)

7 6	8	7	7	NA NA	NA NA	NA	NA	NA	NA	NA NA	NA	NA	NA NA
0.67	0 98	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
135	116	NA	NA	237	433	97	78	51.6	225	117	325	506	212
0.31	0 42	0.1	0.1	_ NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
0.58	0.17	0.17	0.11	NA	NA_	NA	NA	NA	NA	NA	NA.	NA	NA
5	4	8.1	6.7	NA	NA_	NA	NA	NA	NA	NA	NA_	. NA	_ NA
NA	NA	0.8	0.6	NA	NA_	NA	NA	NA	NA	. NA	NA	_ NA	NA
0.0001	0.0001	0.0001	0.0001	NA	_ NA	NΑ							
50	41	NA	NA	NA	NA	NA_	NA	NA	NA	NA	NA _	NA	NA NA
34	21	273	216	NA NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
39	6.9	5.5	2.8	NA	NA	NA_	NA_	NA	NA	NA	NA	NA	NA
0.16	0.1	NA	NA	NA	NA_	NA_	NA	NA NA	NA	NA	NA	NA	NA.
0.043	0.022	0.031	0.02	<0.1	0.002	0.005	0.004	0.004	0.009	0.016	0.02	0.003	0.009
0.64	0.32	0.346	0.235	NA	NA	NA	NA	NA NA	NA	NA	NA	NA NA	NA
52	11	3.05	2.78	NA	NA	NA							
1.3	0.43	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
0.006	0.005	0.001	0.001	NA	NA	NA	NA NA	_NA	NA	NA	NA	NA	NA
0 1	0.024	NA	NA	NA_	NA	NA	NA NA	NA NA	NA	NA	NA	NA	NA
NA	NA	88	98.8	NA	NA	NA_	NA	NA	NA	NA	NA	NA	NA
310	300	NA	NA	NA	NA	NA	NA	NA .	NA	NA	NA	NA	NA
6.4	6.6	NA	NA	NA	NA	NA_	NA	NA	NA	NA	NA	NA NA	NA.
0.73	0.99	0.86	1.11	NA	NA	NA_	NA	NA	NA	NA_	NA NA	NA NA	NA
0 01	0.01	0.1	0.1	NA	NA	NA	NA	NA	NA	NA_	NA	NA NA	NA
4120	1080	2400	538	200	11	233	131	24	54	577	NA	NA NA	113
0 .017	0 026	NA	NA	NA	NA	NA	NA .	NA	ŅĀ	NA	NA	NA NA	NA
0 052	0 032	0.006	0.004	NA	NA	NA_	NA	NA	NA	NA	NA	NA_	NA
0.01	0.01	0.002	0.002	NA	NA	NA	NA .	NA	NA	NA	NA_	NA NA	NA_
9. 9	4	NA NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA .	NA NA
31	18	NA	NA	NA	NA	NA	NA	NA	NA	NA_	NA_	NA_	NA
0 57	0.17	0.202	0.112	NA	NA	NA_	NA_	NA NA	NA	NA	NA	NA .	NA
0.0019	0.001	NA	NA	NA	NA_	NA .	NA NA	NA	NA NA	NA	NA	NA NA	NA NA
0.067	0.017	0.016	0.006	NA	NA	NA	NA NA	NA	NA	NA	NA NA	NA NA	NA
0.046	0.022	NA	NA_	NA	NA	NA NA	NA_	NA	NA .	NA	NA_	NA I	NA.
0 55	0.31	0.362	0.287	NA	NA.	NA	NA NA	NA NA	NA NA	NA	NA	NA NA	NA_
0 16	0.07	0.076	0.051	NA .	NA_	NA_	NA_	NA NA	NA NA	NA NA	NA	NA NA	NA NA
0 24	0.18	NA NA	NA	NA	NA NA	NA NA	NA .	NA NA	NA	NA	NA_	NA NA	NA
0 01	0.01	NA_	NA	NA	NA	NA	NA .	NA NA	NA NA	NA	NA 100	NA 5.70	NA NA
291	200	NA	NA NA	56.5	8.63	15.9	10.2	10.1	10.3	43.3	1.08	5.76	42.6 NA
NA NA	NA NA	147	76	NA_	NA NA	NA NA	NA NA	NA NA	NA	NA NA	NA NA	NA NA	
NA .	NA	NA	NA NA	NA .	NA	NA	NA_	NA NA	NA NA	NA NA	NA_	NA NA	NA NA
AM	NA	NA	NA	NA	NA	NA	NA NA	NA NA	NA NA	NA	NA	NA_	NA

NA Not Analyzed mg/l milligrams per liter

Source: 1998 GBI Sampling Event 1988 IEPA Samples

Table 6: Historical Sampling Results - Storm Water Page 2 of 2

OUTFALL
Туре
Date

	001	001	001	001
- 1			First Flush	COMP
Į	11/19/1981	3/23/1982	6/9/1998	6/9/1998

Parameters

ρН
Fluoride (mg/L)
Sulfate (mg/L)
Ammonia (as N) (mg/L)
Phosphorus-P (T) (mg/L)
BOD5 (mg/L)
FOG (T)
Mercury (T) (mg/L)
Calcium (T) (mg/L)
Sodium (T) (mg/L)
Aluminum (T) (mg/L)
Boron (T) (mg/L)
Cadmium (T) (mg/L)
Copper (T) (mg/L)
Iron (T) (mg/L)
Manganese (T) (mg/L)
Silver (T) (mg/L)
Vanadium (T) (mg/L)
Hardness (mg/L)
(ROE) TDS (mg/L)
Chloride (T) (mg/L)
Nitrate, Nitrite (N Total) (mg/L)
Cyanide T) (mg/L)
TSS (mg/L)
Antimony (mg/L)
Arsenic (T) (mg/L)
Selenium (T) (mg/L)
Magnesium (T) (mg/L)
Potassium (T) (mg/L)
Barium (T) (mg/L)
Beryllium (T) (mg/L)
Chromium (T) (mg/L)
Cobalt (T) (mg/L)
Lead (T) (mg/L)
Nickel (T) (mg/L)
Strontium (T) (mg/L)
Thallium (mg/L)
Zinc (T) (mg/L)
COD (mg/L)
TDS (Conductivity)
Chromium Hexavalent) (mg/L)

NA	7.5	7.2	7.4
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	0.1	0.1
NA	NA	0.05	0 05
NA	NA	4.1	3.7
NA_	_NA	0.1_	0.1
NA	NA	0.0001	0.0001
NA	NA_	NA	NA
NA	NA	NA_	NA
NA	NA	0.253	0.197
NA	0.1	NA	AVI
0.018	<0.005	0.006	0.005
0.03	<0.01	0.007	0.006
3	1.8	0.6	0.438
0.83	0.37	NA	NA
<0.005	< 0.005	0.001	0.001
NA	NA	NA	INA
NA	NA	198	196
NA	514	NA	NA
NA	NA	NA	NA
NA	NA	0.15	0.15
NA	NA	0.1	0.1
NA	NA	20	20
NA	NA	NA	NA
0.002	0.001	0.001	0.001
<0.001	<0.001	0.001	0.001
NA	NA	NA	NA
NA	NA	NA_	NA
0.1	0.1	0.042	0.039
NA	NA	NA	NA
<0.01	<0.05	0.001	0.001
NA	NA	NA	NA
0.14	<0.05	0.017	0.013
0.07	<0.05	0.009	0.008
NA	NA	NA	NA
NA	NA	NA	NA
2.84	2.2	0.947	C.885
NA	NA	88	71
NA	460	NA	NA
NA	0	NA	NA

NA Not Analyzed mg/l milligrams per liter

Table 7: Historical Sampling Results - Groundwater

With the exception of pH, all parameters are measured in mg/L (ppm). Only detect values are presented. All wells sampled on December 1, 1998. Page 1 of 3

Well Number	Lab	Antimony	Arsenic	Barium	Beryllium	Boron	Cadmium	Chromium	Cobalt	Copper	Fluoride
								1 - 2			
G101	PAS	<u> </u>	0.002	0.056				0.014	0.003	0.013	0.58
	IEPA			0.057		0.064	ļ	0.012		0.009	0.52
G102	PAS		0.001	0.109				0.005_	0.002	0.009	0.42
	IEPA_			0.1				0.005			0.41
G103	PAS		0.004	0.124				0.013	0.004	0.013	0.49
3103	IEPA			0.11		0.051		0.012	0.005	0.01	0.48
G104	PAS	0.001	0.006	0.11				0.022	0.006	0.021	0.37
G104	IEPA			0.08		0.1		0.012	0.006	0.016	0.34
G105	PAS			0.09				0.001		0.003	0.33
G105	IEPA			0.088	1						0.3
G106	PAS		0.001	0.037		0.44		0.003	0.001	0.008	0.32
3100	IEPA			0.036		0.38				0.007	0.34
G106 (Duplicate)	PAS	0.001	0.004	0.092		0.42		0.014	0.004	0.013	0.33
	PAS	0.002	0.003	0.071		0.64	0.044	0.002	0.006	0.019	0.52
G107	IEPA							<u> </u>			
6400	PAS		0.003	0.054		0.66	0.029	0.002	0.016	0.017	0.4
G108	IEPA			0.053		0.56	0.032		0.02	0.006	0.38
C400	PAS	0.002	0.003	0.065		0.14		0.012	0.002	0.058	0.54
G109	IEPA			0.059		0.067		0.01		0.058	0.45

Source: Monitoring Wel Installation and GW Sampling Interim Report, March 1999

Table 7: Historical Sampling Results - Groundwater

With the exception of pH, all parameters are measured in mg/L (ppm). Only detect values are presented. All wells sampled on December 1, 1998. Page 2 of 3

Well Number	Lab	Iron	Lead	Manganese	Mercury	Nickel	Selenium	Silver	Thallium	Zinc
G101	PAS	1.98	0.004	0.087		0.008	0.005			0.03
	IEPA	8.9	0.005	0.19		0.01				
G102	PAS	1.82	0.002	0.424		0.005	0.001			0.019
O 102.	IEPA	4.2		0.43						0.12
G103	PAS	3.19	0.007	0.206		0.013	0.002			0.08
	IEPA	12	0.007	0.41		0.014				
G104	PAS	6.62	0.016	0.177		0.019	0.002			0.6
G 104	IEPA	13	0.018	0.38		0.015				0.99
G105	PAS	0.22	0.001	0.204		0.002				0.023
3105	IEPA	1		0.23						
G106	PAS	0.88	0.003	0.061		0.004	0.001			0.038
G 106	IEPA	3.6		0.12						
G106 (Duplicate)	PAS	3.8	0.011	0.215		0.012	0.002			0.104
	PAS	5.96	0.182	2.56		0.005				1.86
G107	IEPA									
0.400	PAS	3.68	0.011	6.1		0.014	0.007			5.34
G108	IEPA	7.7	0.01	6		0.016	1			5.4
0.400	PAS	3.14	0.012	0.124		0.008	0.006			0.058
G109	IEPA	10	0.007	0.025		0.01				

Source: Monitoring Wel Installation and GW Sampling Interim Report, March 1999


411


Table 7: Historical Sampling Results - Groundwater


With the exception of pH, all parameters are measured in mg/L (ppm). Only detect values are presented. All wells sampled on December 1, 1998. Page 3 of 3

Well Number	Lab	Chloride	Cyanide	Nitrate-N	Nitrate, Nitrite	рН	Sulfate	TDS
						7.5	74.0	405
G101	PAS	2.21	 	 	0.40	7.5	71.3	425
	IEPA	2.1	ļi		0.12	7.2	60.8	375
G102	PAS	47.9				7.4	271	700
	IEPA	66.9				7.4	240	650
G103	PAS	51.1	L	0.7		7.3	319	1020
	IEPA	72.6			0.57	7.5	578	610
G104	PAS	31		0.4		7.5	470	995
3.04	IEPA	45.9			0.39	7.2	673	701
G105	PAS	14.6_				7.5	171	535
G103	IEPA	19.8				7.2	171	484
G106	PAS	23.4		0.3		7.5	398	895
G 106	IEPA	30.3				7.9	621	628
G106 (Duplicate)	PAS	23		0.3_		7.4	400	905
G107	PAS	11.5				7.2	410	790
9107	IEPA							
C109	PAS	11.2		0.1_		7	231	675
G108	IEPA	16.7				7.4	204	501
C400	PAS	1.12		0.3		7.7	48	185
G109	IEPA				0.25	6.9	40.9	203

FIGURES







740 Waukegan Road, Suite 401, Deerfield, IL 60015

Site Layout Eagle Zinc Hillsboro, IL

Figure

2

Drafter:

CJG


Date: 1/24/02

Contract Number:

21-7400D

Approved:





ENVIRON

740 Waukegan Road, Suite 401, Deerfield, IL 60015

Shallow Ground Water Contour Map Eagle Zinc, Hillsboro, Illinois Figure 4

Drafter: C

CJG


Date: 01/23/02


Contract Number:

21-7400D

Approved:

Ground Water Contour (elevation in feet above mean sea level)





CPF\Eagle Zi

Drafter:


CJG


Date: 01/23/02

Contract Number:

21-7400D

Approved:





LEGEND

■ 1993 Residue Pile Samples

■ 1998 Residue Pile Samples

740 Waukegan Road, Suite 401, Deerfield, IL 60015

Previous Sampling Locations Residues Eagle Zinc, Hillsboro, Illinois

Figure

8

Drafter:

CJG

Date: 01/23/02

Contract Number:

21-7400D

Approved:

740 Waukegan Road, Suite 401, Deerfield, IL 60015

Previous Sampling Locations Storm Water Eagle Zinc, Hillsboro, IL Figure

9

Drafter:


CJG

Date: 01/23/02

Contract Number:

21-7400D

Approved:



740 Waukegan Road, Suite 401, Deerfield, IL 60015


Potential Areas of Concern On-Site Soil Eagle Zinc, Hillsboro, Illinois Figure 10

Drafter: CJG Date: 01/23/02

Contract Number:

21-7400D

Approved:




INDUSTRIAL PARK DRIVE

EXISTING BUILDING

Rotary Residue Type 1 (Hatched areas depict remaining stockpiles) Rotary Residue Type 2

Miscellaneous

MP1 Piles



OLD FOUNDATION

SMITH ROAD

740 Waukegan Road, Suite 401, Deerfield, IL 60015

Potential Areas of Concern Residues Eagle Zinc, Hillsboro, Illinois Figure 12

Drafter:


CJG


Date: 01/23/02

Contract Number:

21-7400D

Approved:





Potential Areas of Concern

√ 612 Ground Water Contour (elevation in feet above mean sea level)

740 Waukegan Road, Suite 401, Deerfield, IL 60015

Potential Areas of Concern **Ground Water** Eagle Zinc, Hillsboro, Illinois Figure

14

Drafter:

CJG

Date: 01/28/02


Contract Number:


21-7400D

Approved:

ATTACHMENT A
Results of ENVIRON Well Search

One Mile Well Search Eagle Zinc Hillsboro, Illinois










ILLINOIS ENVIRONMENTAL PROTECTION AGENCY

1021 North Grand Avenue East, P.O. Box 19276, Springfield, Illinois 62794-9276 Renee Cipriano, Director

217/782-1020

01/18/2002

Christopher Greco Environ 740 Waukegan Rd., Ste. 401 Deerfield, IL 60015-



Re: Request Regarding the Location of community water supply wells in Montgomery County, Illinois. (FOIA NO: 2002P0033)

Dear Christopher Greco:

This letter responds to your written inquiry received in Public Water Supplies on 01/14/2002 regarding your project area located in the SE ¼ of Section 1 and the NE ¼ of Section 12, T8N, R4W and the SW ¼ of Section 6, T8N, R3W.

You requested information pertaining to the nearest community water supply well. Based upon the information provided, the project area appears to be located outside 2,500 feet from a community water supply well.

Effective September 1st, 2001, the Pleasant Valley Public Water District, in Peoria County, is the first regulated recharge area to designate a defined area with specific regulations in place for the area contributing groundwater to its public water supply wells pursuant to section 17.3 of the Illinois Environmental Protection Act (Act). Further, Class III Special Resource Groundwaters has been listed by the Illinois Pollution Control Board with respect to the contribution to Parker Fen in McHenry County.

The Illinois Department of Public Health should be contacted at (217) 782-5830 in regards to the regulations concerning private, semi-private or non-community public water supply wells and the Illinois State Water Survey should be contacted at (217) 333-9043 in regards to the location of these wells. I trust that this meets your needs. Should you require any further information, please feel free to contact me at the above referenced number.

Sincerely,

Janet Christer

Kut Chuster

FOIA Coordinator, Manager's Office Division of Public Water Supply

Bureau of Water

cc: File

GEORGE H. RYAN, GOVERNOR



Illinois State Water Survey

Main Office • 2204 Griffith Drive • Champaign, IL 61820-7495 • Tel (217) 333-2210 ·· Fax (217) 333-6540

Peoria Office • P.O. Box 697 • Peoria, IL 61652-0697 • Tel (309) 671-3196 • Fax (309) 671-3106



Groundwater Section • Tel (217) 333-4300 • Fax (217) 244-0777

January 11, 2002

Mr. Chris Greco Environ 740 Waukegan Road, Suite 401 Deerfield, IL 60015

Dear Mr. Greco:

As you requested during our telephone conversation on January 11, we are enclosing printouts from our Private Well and Public, Industrial, Commercial Survey (PICS) Databases for the following locations in Montgomery County:

<u>Township</u>	Range	<u>Sections</u>
8 North	4 West	1, 12
8 North	3 West	6

No available information is indicated on the printout by the statement "0 records were found for the specified locations." Also enclosed is an explanation of the Illinois State Water Survey Private Well Database.

The data included in the Private Well Database are those non-municipal wells which are known to the Illinois State Water Survey, and the PICS Database is an inventory of municipal well information and large industrial groundwater users. We may not have a copy of well records for these groundwater users.

The invoice accompanying this request covers the \$35.00 query fee for private well information, \$35.00 query fee for PICS information, and a \$0.10 per page charge for 7 pages, plus a \$5.00 shipping and handling fee, totaling \$75.70.

If you have any questions or if we can be of further assistance, please call.

Sincerely


Susie Dodd-Casey

Associate Supportive Scientist

Groundwater Section Phone: (217) 333-9043

sdc/psl

Enclosures as stated



Inmois State Water Survey Tres backband

Friday, January 11, 2002

County:

MONTGOMERY

Township:

08n

Range:

04w

Sections:

01,12

Records found: 0

Questions:

Contact the Illinois State Water Survey's Ground Water Division @217-333-9043


Publication:

Please cite the Illinois State Water Survey's PICS (Public-Industrial-Commercial)

Database in all publications based wholly or partially on this information.

Note: The data in the PICS Database is a listing of municipal and commercial wells which are known to the Illinois State Water Survey(ISWS). This information was initially entered from public water supply data and supplemented with the Illinois Water Inventory Project data. This database is updated as additional information is received and verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any use of this material.



Location of a 10-acre-plot within a section:

The origin can be found at the lower right-hand-corner of an 8 x 8 grid. In this example, the well is in the 10-acre plot '3d'.

Illinois State Water Survey Private Wen Database

Friday, January 11, 2002

County:

MONTGOMERY

Township:

08n

Range:

()4w

Sections:

01.12

Records found:

Ouestions:

Contact the Illinois State Water Survey's Ground Water Division @217-333-9043


Publication:

Please cite the Illinois State Water Survey's Private Well Database in all publications

based wholly or partially on this information.

Note: The data in the Private Well Database is a listing of non-municipal wells which are known to the Illinois State Water Survey(ISWS). This information has been entered verbatim from well logs submitted by the driller, chemical analysis reports, well sealing forms, well inventory forms from the 1930-1934 well survey, and other special projects. The accuracy of this data is controlled by those submitting the forms. Information in the Private Well Database has not been verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any use of this material.



Location of a 10-acre-plot within a section:

The origin can be found at the lower right-hand-corner of an 8 x 8 grid. In this example, the well is in the 10-acre plot '3d'.

Friday, J	lanuary	11, 2002	2									~~~)WE 4 10	- 10 m	******	***
WID	FIPS	Ч<u>й</u>п	RNG	SEC	PLOT OWNER	DRILLER	DATE DRILLED	DEPTH	RECOR TYPE	D USE	WELL Type	AQUIFER TYPE	STAT LVL	PU' LV	<u>PUMP</u> GPM	
113897	135	08N	04W	01			00/00/1924	22	RG	DO	~~	~				
113898	135	08N	04W	01	······································		00/00/1926	23	RG	DO	~~	~~				
113899	135	08N	04W	01			00/00/1926	60	RG	DO	~~	~				
237419	135	0 8 N	04W	01	CITY OF HILLSBURG HIMW-101	CRANK	09/10/1992	21	RG	МО	-	UN	6			
237420	135	0 8 N	04W	01	CITY OF HILLSBURO HIMW-102	CRANK	09/10/1992	20	RG	МО		UN	6			
237421	135	08N	04W	01	CITY OF HILLSBURO HIMW-103	CRANK	09/10/1992	18	RG	МО		UN	8		· · · · · · · · · · · · · · · · · · ·	
237422	135	08N	04W	01	CITY OF HILLSBURO HIMW-104	CRANK	10/26/1992	14	RG	мо		UN	7	· · · · · · · · · · · · · · · · · · ·		

Illinois State Water Survey PICS Database

Friday, January 11, 2002

County:

MONTGOMERY

Township:

08n

Range:

03w

Sections:

06

Records found: ()

Questions:

Contact the Illinois State Water Survey's Ground Water Division @217-333-9043


Publication:

Please cite the Illinois State Water Survey's PICS (Public-Industrial-Commercial)

Database in all publications based wholly or partially on this information.

Note: The data in the PICS Database is a listing of municipal and commercial wells which are known to the Illinois State Water Survey(ISWS). This information was initially entered from public water supply data and supplemented with the Illinois Water Inventory Project data. This database is updated as additional information is received and verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any use of this material.



Location of a 10-acre-plot within a section:

The origin can be found at the lower right-hand-corner of an 8 x 8 grid. In this example, the well is in the 10-acre plot '3d'.

Illinois State Water Survey Private Well Database Friday, January 11, 2002

County:

MONTGOMERY

Township:

08n

Range:

03w

Sections:

06

Records found: 19

10

Questions:

Contact the Illinois State Water Survey's Ground Water Division @217-333-9043


Publication:

Please cite the Illinois State Water Survey's Private Well Database in all publications

based wholly or partially on this information.

Note: The data in the Private Well Database is a listing of non-municipal wells which are known to the Illinois State Water Survey(ISWS). This information has been entered verbatim from well logs submitted by the driller, chemical analysis reports, well sealing forms, well inventory forms from the 1930-1934 well survey, and other special projects. The accuracy of this data is controlled by those submitting the forms. Information in the Private Well Database has not been verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any use of this material.



Location of a 10-acre-plot within a section:

The origin can be found at the lower right-hand-corner of an 8 x 8 grid. In this example, the well is in the 10-acre plot '3d'.

Friday.	Januar _/	11, 2002	- 404 kgp q ((B)	H 1 D D	H PAR (II i) oj. se ramografio	البوزوان موسود بواسو		-	• •					80 III - pap D	limani-
WID	<u>FIPS</u>	· uniVN	RNG	<u>SEC</u>	PLOT	OWNER	DRILLER	DATE DRILLED	DEPTH	RECOI TYPE	USE	WELL TYPE	AOUIFER TYPE	STAT LVL	PUM^ LV	PUMP GPM
115380	135	08N	03W	06	IE	T COMPAGIN	E BEASLEY	06/05/1978	31	RG	DO	~	~~			
115381	135	08N	03 W	06	lH	R MONTGOMERY	C KOHNEN	07/06/1979	34	RG	DO	~	~			
115382	135	08N	03W	06	1H	B BANDOOR	G E NOLL	07/05/1978	50	RG	DO	~	~~			
115383	135	08N	03W	06	1H	C SHELBAMER	E BEASLEY	11/22/1978	35	RG	ĐO	~~	~~			
115386	135	08N	03W	06	2E	K MASCOLINI	E BEASLEY	12/06/1976	21	RG	DO	~~	~~			
115384	135	08N	03 W	06	2G	W BANDOR	H LINK	09/12/1986	36	RCi	DO	~~	~~			
115385	135	08N	03W	06	211	D CLAYTON	G E NOLL	05/19/1984	29	RG	DO	~	~~			
115387	135	08N	03W	06	2H	D WHITE	C KOHNEN	07/30/1979	35	RG	DO	~	~~			
290674	135	08N	03W	06	3F	KENNETH DEGG	WALTERS	10/09/1996	48	RG	IC	BD	UN			<u>. </u>
115396	135	08N	03W	06	4E	R LASKET	E BEASLEY	08/12/1977	31	RG	DO	~~	~~			
115388	135	08N	03W	06	5E	B ROSENBERGER	E BEASLEY	04/23/1979	32	RG	DO	~	~~			
115389	135	08N	03W	06	5G	J BEOLE	H LINK	08/18/1983	40	RG	DO	~~	~~		<u>-</u>	
15390	135	08N	03W	06	5H	L D FULLER	G BEKEMEYER	00/00/1965	18	RG	DO	~	~			<u></u>
15391	135	08N	03W	06	5H	W M BANDOSS	G BEKEMEYER	08/19/1969	38	RG	DO	~	~~	· · · · · · · · · · · · · · · · · · ·		
15392	135	08N	03W	06	6E	E HUNTON	H LINK	10/22/1987	34 ;	RG	DO	~~	~~			

Fillay.	anuaiy i	1, 200	<u>c</u>										-	———	11.44	rem 9 m-
WID	FIP\$	<u>.wn</u>	RNG	SEC	PL.OT	OWNER	DRILLER	<u>DATE</u> <u>DRILLED</u>	DEPTH	RECOR TYPE	D USE	WELL TYPE	AQUIFER STAT TYPE LVL	PU"	<u>PUMP</u> <u>GPM</u>	
115393	135	08N	03W	06	6F	J LETVENAS	H LINK	10/25/1987	40	RG	DO	~~	~			- 1
198886	135	08N	03W	06	6F	JOHN KUNZ	BEASLEY	05/01/1980	24	RG	DO	BD	UN			
115394	135	08N	03W	06	7H	J RAMBO	C WILSON	01/13/1976	32	RG	DO	~~	~	······································		
115395	135	08N	03W	06	8H	N MC WILLIAMS	G BEKEMEYER	06/29/1968	10	RG	DO	~~	~~			

;

ISWS 10-ACRE PLOT LOCATION SYSTEM


The following is an explanation of the ISWS Private Well Database location system.

The location system uses Township, Range, and Section. The location consists of five parts: County abbreviation, Township, Range, Section, and coordinate within the section (subsection or 10-acre plot). Sections are divided into rows of 1/8-mile squares. Each 1/8-mile square contains 10 acres and corresponds to a quarter of a quarter of a quarter section. A normal section of 1 square mile contains 8 rows of 1/8-mile squares; an odd-sized section contains more or fewer rows. Rows are numbered from east to west and lettered from south to north as shown in the diagram.

Example:

St. Clair County, FIP No. 163

T2N, R10W Section 23



The location of the well shown above is 163 2N10W-23.4c. The well point is located at the center of this 10-acre plot.

ILLINOIS STATE WATER SURVEY PRIVATE WELL DATABASE EXPLANATION

WID Illinois State Water Survey Identification Number

FIPS County Code Number

TWN Civil Township

RNG Range SEC Section

HH

PLOT 10-acre Plot Location within the Section

OWNER Well Owner

DRILLER Well Drilling Contractor of Well

DATE DRILLED Date Initially Drilled
DEPTH Depth (well to nearest ft)

RECORD TYPE Record Type (types of information on file)

R - Construction Report

G - Geology S - Sealed

A - Affidavit

C - Chemical Analysis

I - Inventory

X - Indicates Comment in Owners Field Something Unusual

O - Any Other Type of Record

P - Pump Installation

USE Well Use (two-letter code indicating the usage of the well)

CO - Conservation

CS - Community Supply

DO - Domestic

DW - De-Watering

IC - Industrial/Commercial

IN - Injection Well

IR - Irrigation

MO - Monitoring

NC - Non-Community

NW - Non-Well Source

OB - Observation

PK - Park

RC - Recovery Well

RW - Relief Well

SC - School

ST - State

USE

(Continued)

TB - Test Boring
TH - Test Hole
TW - Test Well
- Unknown

WELL TYPE

Well Type (two-letter code indicating the type of well)

BLANK - Assumed Drilled

BD - Bored DL - Drilled

DU - Dug (Being Phased Out)

DR - Driven
NW - Non-Well
SP - Sand Point
SG - Spring

Assumed Drilled or Possibly Unknown

AQUIFER TYPE

Aquifer Type (two-letter code indicating aquifer type)


BR - Bedrock
DH - Dry Hole
SW - Surface Water
UN - Unconsolidated
- Unknown

STAT LVL PUMP LVL PUMP GPM Static Level - Reported non-pumping water level

Pumping Level - Reported water level during initial pumping of the well

Pumping GPM - Gallons per minute at time of well construction


THE DATA IN THE PRIVATE WELL DATABASE IS A LISTING OF THE NON-COMMUNITY WELLS WHICH ARE KNOWN TO THE ILLINOIS STATE WATER SURVEY (ISWS). THIS INFORMATION HAS BEEN ENTERED VERBATIM FROM WELL LOGS SUBMITTED BY THE DRILLER, FROM CHEMICAL ANALYSIS REPORTS, FROM WELL SEALING FORMS, OR WELL INVENTORY FORMS FROM THE 1930-34 WELL SURVEY AND OTHER SPECIAL PROJECTS. THE ACCURACY OF THIS DATA IS CONTROLLED BY THOSE WHO SUBMITTED THE FORM. INFORMATION IN THE PRIVATE WELL DATABASE HAS NOT BEEN VERIFIED.



ATTACHMENT BResults of Previous Well Searches

Illinois Geological Survey Water Well Search

Map Area: 8N-4W-12 m3 to 9N-3W-31 m3



N									
•	Oil	X	Gas Injection	Q	Junked				
*	Oil & Gas	0	Gas Storage	¢	Temporarity Abandone				
*	Gas	•	Salt Water Disposal	•	Observation				
÷	D&A - Oil Show	ø	Water injection	æ	Other Injection				
₩	D&A - Gas Show	A	Water Supply	0	Confidential				
*	D&A - Oil & Gas Show	0	Permit	M	Other Well Type				
ራ	D&A	δ	Water	+	Status Unknown				



التحريبية المراجعة		
00	1209	2418 ft
Illine	ois State Geolog	gical Survey
QuE	StoR: Cust	om Map
Date: 28	JUN-00 Scale:	1:14508

Displayed data is based upon information supplied to the Illinois State 'Geological Survey (ISGS) and are not field verified. The ISGS does not guarantee the validity, accuracy or completeness of these data. Non Oil and Gas - Wells

```
Link, Harold F.
121352281300
                                                                   6- 8N- 3W
                     Bandor, William
Montgomery
Status: WATER
                                         SW N : NE
                                                        Elev:
                         permit date: 09/10/36
                                                       comp. date: 09/12/86
producing formation: latitude 30 17266
permit: 126708
                                                        td: 36
                            longitude: 89.459721
latitude: 39.170697
latitude: 39.170697 longitude: 49.4 Water from sand at depth 18 to 36 ft.
Screen: Diam. 0 in. Length: 0 ft. Slot: 0
Casing and Liner Pipe -
      Diam. (in.) Kind and Weight
                                             From(ft)
                                                           To (ft.)
                         PLASTIC
                                                      0
         36
                         CONCRETE
                                                       n
                                                                  36
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is
                                                          0 ft. above grnd level.
Pumping level
                    0 ft. when pumping at
                                                 0 gpm for 0 hours.
Formations Passed Through
                                                 Thickness Bottom
                                                   13
                                                           13
  gravely clay
                                                   5
                                                               18
  sand
                                                   18
                                                               36
                Bekemeyer, Gust
Bandor, Wm
121350166600
                                                                   6- 8N- 3W
Montgomery
Status: WATER
                                        NE NE NW
                                                        Elev:
Lambert X: 3009280 Lambert Y
                                                       comp. date: 08/19/69
Lambert X: 3009280 Lambert Y: 2238792
producing formation: td formation:
latitude: 39.172499 longitude: 89.467089
Water from sand at depth 0 to 0 ft.
Screen: Diam. in. Length: 0 ft. Slot:
                                                         td: 38
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                            From(ft)
         48
                        CONCRETE
Size hole below casing: in.
Static level 20 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                Thickness Bottom
                                                            20
  clay
                                                  20
  sand
                                                   6
                                                               26
  clay
                                                   12
                                                               38
121352288200 Link, Harold F.
                                                           6- 8N- 3W
Montgomery Berle, James
Status: WATER SE NE NW permit: 108354 permit date: 07/28/83 Lambert X: 3009284 Lambert Y: 2238134
                                                       Elev:
                                                      comp. date: 08/18/83
                       Lambert Y: 2238134
                                                        td: 40
producing formation:
                                     td formation:
latitude: 39.170685 longitude: 89.466079 Water from gravel at depth 16 to 20 ft.
Screen: Diam. 0 in. Length: 0 ft.
                                              Slot: 0
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                            From(ft)
                                                           To(ft)
                        PLASTIC
        6
        36
                         CONCRETE
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                Thickness Bottom
                                                  16
                                                              16
  gravel & clay mix
                                                   4
                                                              20
  clay
                                                   6
                                                              26
  gray clay
                                                  14
                                                               40
```

```
121352241100
                    Noll, Gary E.
                                                               6--8N- 3W
 Montgomery
                    Clayton, Debby
 Status: WATER
                                      NW NE NE
                                                     Elev:
 permit: 110792
                       permit date: 12/09/82
                                                   comp. date:
 Lambert X: 3011260
                       Lambert Y: 2238792
                                                     td:
 producing formation:
                                     td formation:
 latitude: 39.172497
                              longitude: 89.459734
latitude: 39.1/249/ Iongitude: 89.439/34 Water from clay at depth 0 to 0 ft. Screen: Diam. 0 in. Length: 0 ft. Slot: 0
 Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                                       To(ft)
                                           From(ft)
                        CONCRETE
 Size hole below casing: 0 in.
Static level 0 ft. below casing top which is
                                                       0 f.t. above grnd level.
                0 ft. when pumping at 0 gpm for
Pumping level
                                                                0 hours.
                                             Thickness Bottom
Formations Passed Through
  clay
                                               29
                                                          29
121352380600
                   Walters, Steven
                                                               6- 8N- 3W
Montgomery
                   Degg, Kenneth
Status: WATER
                                     NE SW NE
                                                     Elev:
                     permit date: 08/30/96
permit:
                                                   comp. date: 10/09/96
Lambert X: 3010608
                      Lambert Y: 2237484
                                                     td:
                                                          48
producing formation:
latitude: 39.168887
                                     td formation:
                             longitude: 89.462382
Water from gravel - gray sand at depth Screen: Diam. in. Length: 0 ft.
                                          24 to
                                                     45 ft.
                                           Slot:
Casing and Liner Pipe -
                     Kind and Weight
     Diam. (in.)
                                          From(ft)
                                                       To(ft)
                                                   0
        6
                       PLASTIC
        36
                       CONCRETE
                                                              48
Size hole below casing: in.
Static level 0 ft. below casing top which is
                                                      0 ft. above grnd level.
Pumping level
                   0 ft. when pumping at
                                              0 gpm for 0 hours.
Formations Passed Through
                                             Thickness Bottom
  clay
                                                6
                                                           6
  red sandy clay
                                                3
  gravelly clay
                                                7
                                                          16
  hardpacked gravelly clay
                                                8
  hardpacked gravel
                                                5
                                                          29
  gray gravelly clay
                                               10
  layered gray gravelly sand & gray clay
                                                6
  gray gravelly clay
                 Hayes, C.M.
121352343200
                                                              6- 8N- 3W
Montgomery .....
                 Ewald
                                                   .....1 -59
Status: WTST 2000 NL 3000 EL
                                       NE
                                                    Elev:
                                                                 0
                    permit date:
permit:
                                                   comp. date:
Lambert X: 3009260
                      Lambert Y: 2237121
                                                    td: 0
producing formation:
                                   td formation:
latitude: 39.167886 longitude: 89 Water from at depth 0 to 0 ft.
latitude: 39.167886
                             longitude: 89.467162
Screen: Diam. in. Length:
                                  0 ft.
                                           Slot:
Casing and Liner Pipe -
     Diam. (in.)
                   Kind and Weight
                                          From(ft)
                                                      To(ft)
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd level.
                0 ft. when pumping at
Pumping level
                                             0 gpm for 0 hours.
Formations Passed Through
                                            Thickness Bottom
  S.S. #33227 (110-165')
121350120100
                   Bekemeyer, Gust
                                                              6 - 8N - 3W
Montgomery
                   Fuller, Drix
Status: WATER
                                     NE NE NW
                                                    Elev:
permit: NF 4522
                      permit date: 01/01/68
                                                  comp. date: 01/01/68
```

td:

18

Lambert Y: 2238792

Lambert X: 3009280

```
producing formation: td formation: latitude: 39.172499 longitude: 89.467089
 Water from sand at depth 15 to 19 ft.
 Screen: Diam. in. Length: 0 ft.
 Casing and Liner Pipe -
       ng and Liner Fipe -
Diam. (in.) Kind and Weight From(ft) To(ft)

AR CONCRETE 1 1
                            CONCRETE
 Size hole below casing: in.
 Static level 15 ft. below casing top which is 1 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
 Formations Passed Through
                                                          Thickness Bottom
   clay
                                                            12
                                                                       12
   sand
                                                                          18
121352312600 Link, Harold F.

Montgomery Huston, Earl Jr.

Status: WATER SW SE NW

permit: 136436 permit date: 10/20/87

Lambert X: 3008632 Lambert Y: 2236813

producing formation: td formation:
latitude: 39.167036 longitude: 89.469390

Water from gravel at depth 18 to 34 ft.
                                                                               6- 8N- 3W
                                                                 Elev:
                                                                comp. date: 10/22/87
                                                                   td: 34
Screen: Diam. 0 in. Length: 0 ft.
                                                      Slot: 0
Casing and Liner Pipe -
       Diam. (in.) Kind and Weight From(ft)
                                                                     To(ft)
                          PLASTIC
                                                       0
          36
                             CONCRETE
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                         Thickness Bottom
Formations Passed Through
   clay
                                                            18 18
                                                            16
   gravel
121352288300 Beasley, Eugene B. Montgomery Kunz, John
                                                                              6- 8N- 3W
Status: WATER
permit: 93560
Lambert X: 3008628
Lambert Y: 2237473
td formatio
                                               NW SE NW Elev: 0
04/29/80 comp. date: 05/01/80
                                                                   td: 24
producing formation: td formation: latitude: 39.168864 longitude: 89.468194 Water from sand at depth 16 to 24 ft.
Screen: Diam. 0 in. Length: 0 ft. Slot: 0
Casing and Liner Pipe -
      CONCRETE
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                         Thickness Bottom
                                                                16
  clay
                                                           16
   sand to hardpan
                                                             8
121352312700 Link, Harold F.
                                                                              6- 8N- 3W
Montgomery
                       Latvenas, Joe
Status: WATER

permit: 136499

Lambert X: 3008628

producing formation:
latitude: 39.168864

NW SE NW

Elev: 0

comp. date: 10/26/87

td: 40

longitude: 89.468194
Status: WATER
latitude: 39.168864 longitude: 89.468194
Water from gravel at depth 15 to 17 ft.
Screen: Diam. 0 in. Length: 0 ft. Slot: 0
Casing and Liner Pipe -
      Diam. (in.) Kind and Weight From(ft)
                                                                      To(ft)
          6
                             PLASTIC
          36
                              CONCRETE
```

```
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is 0 ft. above grnd level.
                 0 ft. when pumping at
                                             0 gpm for 0 hours.
Pumping level
Formations Passed Through
                                             Thickness Bottom
  clay
                                               15
                                                         15
                                                2
  gravel
                                                          17
  gray clay
                                               23
                                                          40
121352236800
                   Beasley
                                                               6- 8N- 3W
Montgomery
                   Lockot, Robert
Status: WATER
                                      SW SW NE
                                                     Elev:
permit: 64891
                      permit date: 08/08/77
                                                   comp. date: 08/12/77
Lambert X: 3009952
                       Lambert Y: 2236824
                                                     td: 31
producing formation:
latitude: 39.167065
                                     td formation:
                            longitude: 89.464709
Water from sand at depth 13 to 15 ft.
Screen: Diam. in. Length: 0 ft.
                                            Slot:
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                           From(ft)
                                                       To(ft)
        36
                       CONCRETE
                                                   n
                       PLASTIC
                                                             10
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                       0 ft. above grnd level.
Formations Passed Through
                                             Thickness Bottom
  clay
                                               13
                                                          1,3
  sand
                                                2
                                                          1.5
  hardpan
                                               16
                                                          31
121352288400
                   Beasley, Eugene B.
                                                              6~ 8N- 3W
Montgomery
                   Marcolini, Kelly
Status: WATER
                                     SW SE NE
                                                    Elev:
permit: 55284
                    permit date: 11/30/76
                                                   comp. date: 12/06/76
Lambert X: 3011272
                      Lambert Y: 2236835
                                                    td: 21
producing formation:
                                    td formation:
latitude: 39.167094 longitude: 89.459698 Water from gravel at depth 15 to 21 ft.
Screen: Diam. 0 in. Length: 0 ft.
                                           Slot: 0
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                          From(ft)
        6
                      PLASTIC
                                                   0
                                                             10
        36
                      CONCRETE
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is Pumping level 0 ft. when pumping at 0 gr
                                                       0 ft. above grnd level.
                                                0 gpm for
                                                               0 hours.
Formations Passed Through
                                             Thickness Bottom
 clay
                                                          15
                                               15
 gravel
                                                6
                                                          21
121350162200
                                                              6- 8N- 3W
                 McWilliams, Neal
Montgomery
Status: WATER
                                     NW NW NW
                                                    Elev:
                    permit date: 01/01/68
permit: NF 4134
                                                   comp. date: 06/29/68
Lambert X: 3007770
                      Lambert Y: 2238792
                                                    td: 37
producing formation:
                                    td formation:
                         longitude: 89.472444
0 to 0 ft.
latitude: 39.172500
                                      0 ft.
Water from sand at depth
Screen: Diam. in. Length: 0 ft.
                                           Slot:
Casing and Liner Pipe -
     Diam. (in.)
                     Kind and Weight
                                          From(ft)
                                                       To(ft)
        48
                       CONCRETE
Size hole below casing: in.
Static level 20 ft. below casing top which is
                                                       1 It. above grnd level.
Pumping level
              0 ft. when pumping at
                                                0 gpm for
                                                               0 hours.
Formations Passed Through
                                            Thickness Bottom
 clay
                                               18
                                                          18
  sand
                                                          27
```

gravel

hardpan

blue clay

37

```
121352315600 Link, Harold F.
                                                                                6- 8N- 3W
 Montgomery
                       Mutchler, Jim
 Status: WATER
                                                NW NW SE
                                                                  Elev:
 permit: 001867 permit date: 05/12/88
Lambert X: 3009956 Lambert V: 2226160
                                                                 comp. date: 06/01/88
                                                                  td: 65
 producing formation:
latitude: 39.165260
                                               td formation:
 latitude: 39.165260 longitude: 89.463933
Water from gravel at depth 17 to 59 ft.
Screen: Diam. in. Length: 0 ft. Slot:
 Casing and Liner Pipe -
       Diam. (in.) Kind and Weight From(ft)
                                                                      To(ft)
                                                       0
                             PLASTIC
           36
                             CONCRETE
 Size hole below casing: in.
 Static level 0 ft. below casing top which is 0 ft. above grnd Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                                 0 ft. above grnd level.
 Formations Passed Through
                                                         Thickness Bottom
   clay
                                                           15
                                                                          15
   gravel & clay
                                                             3
                                                                          18
   yellow sand clay
                                                            8
                                                                          26
   gray clay
                                                           15
                                                                         41
   gray gravel & clay mix
                                                            2
                                                                         43
   gray clay
                                                            11
                                                           5
   gray gravel
                                                                          59
   gray clay
                      Wilson, Carl
121352201600
                                                                               6-8N-3W
Montgomery
                       Rambo, John
Status: WATER
                                              NE NW NW
                                                                 Elev:
Lambert X: 3007960 Lambert V
                                                                comp. date: 01/13/76
Lambert X: 3007960 Lambert Y: 2238792 producing formation: td formation: latitude: 39.172500 longitude: 89.471771 Water from clay at depth 0 to 0 ft. Screen: Diam. in. Length: 0 ft. Slot: Casing and Liner Pipe
                                                                   td: 32
Casing and Liner Pipe -
      Diam. (in.) Kind and Weight
                                                   From(ft)
          30
                          CONCRETE
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                         Thickness Bottom
                                                           32
                                                                      32
                                                        ....
  .....
121352245600 Beasley
Montgomery Rosenberger, Bob
Status: WATER
permit: 83958 permit date: 03
                                                                            6- 8N- 3W
permit: 83958 permit date: 03/15/79
Lambert X: 3009292 Lambert Y: 200117
                                                               Elev: 0
                                               SE SE NW
                                                              comp. date: 04/23/79
Lambert X: 3009292 Lambert Y: 2236818 producing formation: td formation: latitude: 39.167050 longitude: 89.467049 Water from gravel at depth 16 to 20 ft.
                                                                   td: 32
Screen: Diam. in. Length: 0 ft.
                                                       Slot:
Casing and Liner Pipe -
      Diam. (in.) Kind and Weight
                                                   From(ft)
                          PLASTIC
                                                         0
                            CONCRETE
Size hole below casing: in.

Static level 0 ft. below casing top which is 0 ft. above grnd level.

Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                        Thickness Hottom
                                                                         16
```

20

26

```
121352288600
                  Kohnen, Clarence
                                                            6- 8N- 3W
                 White, Douglas
Montgomery
Status: WATER
                  119 SL 139 WL
                                      NW NE NE
                                                   Elev:
                   permit date: 07/26/79
permit: 88057
                                                comp. date: 07/30/79
                      Lambert Y: 2238585
Lambert X: 3011070
                                                  td: 35
producing formation:
                                   td formation:
latitude: 39.171925
                           longitude: 89.460298
Water from red sand & clay at depth 25 to 28 ft.
Screen: Diam. 0 in. Length: 0 ft. Slot: 0
Casing and Liner Pipe -
     Diam. (in.)
                    Kind and Weight
                                       From(ft)
                                                    To(ft)
        36
                      CONCRETE
Size hole below casing: 0 in.
Static level 0 ft. below casing top which is
                                                    0 ft. above grnd level.
Pumping level
                0 ft. when pumping at
                                            0 gpm for
                                                         0 hours.
Formations Passed Through
                                           Thickness Bottom
  top soil
                                             1
                                                       1
  clay
                                             24
                                                       25
  red sand clay
                                              3
                                                       28
                                                     · 35
                                              7
  blue clay
121350008300
                  Hillsboro Well
                                                           1- 8N- 4W
Montgomery
                  Herguth, Fernine
Status: COAL
                                                  Elev:
permit: 0
                     permit date:
                                                comp. date: 09/01/14
Lambert X: 3004856
                     Lambert Y: 2236468
                                                  td: 570
producing formation:
                                   td formation:
latitude: 39.166087
                            longitude: 89.482780
Water from at depth 0 to
                                0 ft.
Screen: Diam. in. Length:
                                 0 ft.
                                         Slot:
Casing and Liner Pipe -
     Diam. (in.)
                   Kind and Weight
                                       From(ft)
                                                   To(ft)
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd level.
Pumping level
                0 ft. when pumping at
                                            0 gpm for
                                                        0 hours.
Formations Passed Through
                                           Thickness Bottom
  soil & clay
                                            10
                                                      10
  quick sand
                                            15
                                                       25
  shale
                                            43
                                                       68
  sand rock little water
                                            10
                                                      78
  shale
                                           307
                                                      385
  coal
                                             2
                                                      387
                                            38
  shale
121352343500 Layne Western Co.
                                      .... 1- 8N- 4W- ....
Montgomery Hillsboro
                                                     3--54
Status: WTST
               1500 SL 800 WL
                                                    Elev:
                   permit date:
permit:
                                                comp. date:
Lambert X: 3003052 Lambert Y: 2235340 producing formation: td formation: latitude: 39.162974 longitude: 89.489178 Water from at depth 0 to 0 ft.
                                                  td:
Screen: Diam. in. Length:
                                0 ft.
                                        Slot:
Casing and Liner Pipe -
    Diam. (in.) Kind and Weight
                                     From(ft)
                                                    To(ft)
Size hole below casing: in.
Static level 0 ft. below casing top which is
                                                  0 ft. above grnd level.
                0 ft. when pumping at
Pumping level
                                          0 gpm for 0 hours.
Formations Passed Through
                                          Thickness Bottom
  S.S. #24537 (0-92')
                                             n
121352362800
                  Crank, Tim / Marlo John
                                                           1- 8N- 4W
Montgomery
                  Hillsboro, City of
                                                     HIMW-101
Status: MONIT
                                   NW SW
                                                  Elev: 567GL
```

-6~

comp. date: 09/10/92

permit date:

permit: none

```
Lambert X: 3002899 Lambert Y: 2235809
producing formation: td formation:
latitude: 39.164268 longitude: 89.489720
Water from sand at depth 8 to 15 ft.
                                                            td:
 Screen: Diam. 6 in. Length: 15 ft.
                                                Slot: 10
 Casing and Liner Pipe -
      Diam. (in.) Kind and Weight
                                              From(ft)
          6
                         PVC SCH 40
                                                     -3
 Size hole below casing: in.
 Static level 9 ft. below casing top which is 3 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                   Thickness Bottom
 Formations Passed Through
                                                               8
   gray-brown silty clay
                                                      8
                                                       7
   clayey sand w/trace gravel
                                                                  15
   gray-brown sandy clay (till)
                                                                  21
121352362900 Crank, Tim / Marlo John
                                                                       1- 8N- 4W
                                                        HIMW102
                     Hillsboro, City of
Montgomery
                                         · NW SW
Status: MONIT
                                                           Elev: 567GL
                        permit date:
permit: none
                                                         comp. date: 09/10/92
Lambert X: 3002899 Lambert Y: 2235809 producing formation: td formation: latitude: 39.164268 longitude: 89.489720 Water from and at depth 7 to 15 ft.
                                                            td: 20
Screen: Diam. 6 in. Length: 15 ft.
                                                Slot: 10
Casing and Liner Pipe -
      Diam. (in.) Kind and Weight From(ft)
6 PVC SCH 40 -3
                                                            To(ft)
Size hole below casing: in.
Static level 9 ft. below casing top which is 3 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                   Thickness Bottom
Formations Passed Through
  silty clay, gray brown
                                                     7
                                                               7
  clayey sand w/trace gravel
  gray -brown sandy clay (till)
                                                      5
                                                                  20
                                                        1-
HIMW103
121352363000 Crank, Tim / Marlo John
                                                                      1- 8N- 4W
                    Hillsboro, City of
Montgomery
permit: none
                                         NW SW
                                                          Elev: 567GL
permit: none permit date:
Lambert X: 3002899 Lambert Y: 2235809
                                                         comp. date: 09/10/92
                                                            td: 19
producing formation: td formation: latitude: 39.164268 longitude: 89.489720 Water from sand at depth 7 to 17 ft.
Screen: Diam. 2 in. Length: 10 ft. Slot: 10
Casing and Liner Pipe -
Diam. (in.) Kind and Weight From(ft)
                                                              To(ft)
                        PVC SCH 40
Size hole below casing: in.
Static level 8 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                  Thickness Bottom
  gray-brown silty clay
                                                          7
  gray clayey sand, trace gravel
                                                     10
                                                                  17
  gray-brown sandy clay
                                                     1
                                                                 18
                 Crank, Tim / Marlo John
                                                        1-
HIMW104
121352363100
                                                                      1- 8N- 4W
Montgomery
                    Hillsboro, City of
                                        NW SW
Status: MONIT
                                                          Elev: 567GL
permit: none permit date:
Lambert X: 3002899
producing formation:
                                                       comp. date: 10/26/92
                                                           td: 14
producing formation: latitude: 39.164268
producing formation: td formation: latitude: 39.164268 longitude: 89.489720 Water from at depth 0 to 0 ft.
Screen: Diam. 2 in. Length:
                                       0 ft. Slot: 10
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight
                                              From(ft) To(ft)
```

```
PVC SCH 40
 Size hole below casing: in.
Static level 7 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                 Thickness Bottom
  black silty clay
                                                               6
                                                                10
  gray silt clay, trace sand & gravel
                                                     4
  gray-black silty clay, tr/sand & gravel
                                                               11
  fine coarse sand w/clay till
                                                               12
  grav till
121352316400 Link, Harold F. Montgomery Petcher, Thomas
                                                                    1- 8N- 4W
NW NW NE
permit: 002511 permit date: 06/03/88
Lambert X: 3005165 Lambert Y: 2238777
producing formation: latitude: 39 172465
Status: WATER
                                                         Elev: 0
                                                       comp. date: 06/14/88
                                                          td: 32
latitude: 39.172461
Water from
                                        td formation:
                               longitude: 89.481683
Water from gravel at depth 16 to 18 ft.
Screen: Diam. in. Length: 0 ft. Slot:
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight From(ft)
                                                            To(ft)
                                                       Ó
                         PLASTIC
         36
                         CONCRETE
                                                        0
                                                                   32
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
Formations Passed Through
                                                 Thickness Bottom
                                                            16
                                                   16
                                                    2
  yellow gravel
                                                               18
  gray clay
                                                   14
                                                               32
121350015400
                   Sullivan Machine Co
                                                                   1- 8N- 4W
Montgomery
Status: COAL 2450 SL 1300 WL
                                                          Elev: 561GL
producing formation: td formatitude: 39.165590
                    permit date:
                                                      comp. date:
                                                         td: 1
                                       td formation:
                              longitude: 89.487447
121350007900 Hillsboro Mine
Montgomery Hillsboro Mine
                                                                   12- 8N- 4W
Status: COAL
                                                        Elev: 632GL
permit: 0 permit date:
Lambert X: 3004875 Lambert Y: 2231197
                                                       comp. date:
                                                         td: 438
producing formation: td formation: latitude: 39.151535 longitude: 89.482716 Water from at depth 0 to 0 ft.
Screen: Diam. in. Length:
                                     0 ft.
                                               Slot:
Casing and Liner Pipe -
     Diam. (in.) Kind and Weight From(ft)
                                                          To(ft)
Size hole below casing: in.
Static level 0 ft. below casing top which is 0 ft. above grnd level. Pumping level 0 ft. when pumping at 0 gpm for 0 hours.
                                                  0 gpm for 0 hours.
Formations Passed Through
                                                Thickness Bottom
  clay sand, yellow & pebbles
                                                            14
                                                   14
                                                   23
  hardpan
                                                               37
                                                   1
                                                              38
  quicksand
  hardpan
                                                   16
                                                              54
  clay, yellow
                                                   7
                                                              61
  sand gravel
                                                   21
  clay, blue
                                                   26
                                                             108
  sand, coarse
                                                   3
                                                             111
  sand, coarse & gravel
                                                   13
                                                              124
                                                            132
  limestone, hard & broken
                                                   8
  clay shale
                                                              167
  clay, hard & shale
                                                   17
                                                              184
```

_		
limestone	1	185
shale, bituminous	1	136
coal nog	1	187
clay shale	9	196
clay shale w/ hard bands	20	216
sand shale	55 ·	271
sand shale w/ limestone bands	8	279
sandstone	2	281
fire clay	8	289
shale, sandy	24	313
slate	78	391
shale, conglomerate	5	396
clay chale	Λ	400

Montgomery County: - Private Well Database - Page 2

Thursday Jun 29 19100 15:15:16

(OFFICE) (USE ONLY)	FTPS	TWN	RNG	SC	PL (OWNER	<u> </u>	:			DRILLER	DATE	PERMIT	пртн	REC	ບຣ	TY	AO
113897	135	08N	04W	01								00/00/1924	1	22	RG	DO	~~	~~
113898	135	08N	04W	01								00/00/1926	İ	23	RG	DO	~~	~~
113899	135	08N	04W	01				:				00/00/1926	į	60	RG	DO	~~	~~
237419	135	08N	04W	01		CITY	OF	HILLSBURO	HIMW-10	1	CRANK	09/10/1992	•	21	RG	MO		UN
237421	135	08N	04W	01		CITY	OF	HILLSBURO	HIMW-10	3	CRANK	09/10/1992		18	RG	MO		UN
237420	135	08N	04W	01		CITY	OF	HILLSBURO	HIMW-10	2	CRANK	09/10/1992		20	RG	MO		UN
237422	135	08N	04W	01		CITY	OF	HILLSBURO	HIMW-10	4	CRANK	10/26/1992		14	RG	MO		UN

Illinois State Water Survey PICS Database Page 1 Thursday Jun 29 19100 15:15:38

Query the PICS Database through the World Wide Web http://gwinfo.sws.uiuc.edu/gwdb-query.html

County: Montgomery

Township Code: 8N Range Code: 4W Section Codes: 1

O records were found for the specified locations.

Questions : Contact the Illinois State Water Survey's

Ground Water Division @ (217)333-7223

Publication: Please cite the Illinois State Water Survey's

PICS (Public-Industrial-Commercial) Database in all publications based wholly or partially


on this information.

Please Note:

The data in the PICS Database is a listing of municipal and large industrial and commercial wells which are known to the Illinois State Water Survey (ISWS). The information was initially entered from public water supply data and supplemented with the Illinois Water Inventory Project data. This database is updated as additional information is received and verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any publication of this material.

Location of 10-acre-plot within a Section



h The origin can be found at the g lower-right-hand corner of an f 8 x 8 grid. In this example, e the well is in 10-acre plot 3d.



Illinois State Water Survey

Main Office • 2204 Griffith Drive • Champaign, IL 61820-7495 • Tel (217) 333-2210 • Fax (217) 333-6540

Peoria Office • P.O. Box 697 • Peoria, IL 61652-0697 • Tel (309) 671-3196 • Fax (309) 671-3106



Ground-Water Section • Tel (217) 333-4300 • Fax (217) 244-077.7

July 5, 2000

Mr. Mark Milward Philip Environmental Services 210 W. Sandbank Road Columbia, IL 62236

Dear Mr. Milward:

As you requested during our telephone conversation on June 30, we are enclosing printouts from our Private Well and Public, Industrial, Commercial Survey (PICS) Databases for Section 1 of Township 8N., Range 4W., in Montgomery County.

No available information is indicated on the printout by the statement "0 records were found for the specified locations." Also enclosed are explanations of the Illinois State Water Survey Private Well and PICS Databases.

The data included in the Private Well Database are those non-municipal wells which are known to the Illinois State Water Survey, and the PICS Database is an inventory of municipal well information and large industrial ground-water users. We may not have a copy of well records for these ground-water users.

The invoice accompanying this request covers the \$20.00 query fee for private well information, \$20.00 query fee for PICS information, and a \$0.10 per page charge for 3 pages, plus a \$5.00 shipping and handling fee, totaling \$45.30.

If you have any questions or if we can be of further assistance, please call.

Sincerely,

Susie Dodd-Casey

Assistant Supportive Scientist

Quesia Oodd-Casey

Ground-Water Section

Phone: (217) 333-9043

sdc/psh

Enclosures

INVOICE

ILLINOIS STATE WATER SURVEY

2204 Griffith Drive Champaign, IL 61820-7495 (217) 333-4300

Fax: (217) 244-0777

SOLD TO:

Mark Milward

Philip Environmental Services 210 W. Sandbank Road

Columbia, IL 62236

SHIP TO:

INVOICE NUMBER: INVOICE DATE:

GW00-507

July 6, 2000

CUSTOMER REF. NO.:

SALES PERSON:

sdc

DESCRIPTION **THUOMA**

Private Well Database Que

PICS Database Query

Page charge for 3 pages @ \$

\$20.00

\$20.00

\$0.30

SUBTOTAL S&H

TOTAL DUE

\$40.30 \$5.00 \$45.30

MAKE CHECK PAYABLE TO: ÎL STATE WATER SURVEY

Attention: Administration

NET 30 DAYS

Please return COPY with payment

For Accounting Use Only: Credit Acct. #1-3-60977-002, Dept. G

ILLINOIS STATE WATER SURVEY PICS DATABASE EXPLANATION

SWS ID

ISWS facility ID number

Name

Facility name

No.

ISWS point source well/intake number

Status

Point source status of well/intake

A = Abandoned - no longer in existence, no affidavit on file, or do not know if it has been filled in

C = Capped - cap attached to top

D = Disconnected - disconnected from system
E = Emergency - available for standby use

I = In Use - produces major portion of water

O = Observation - used for water level measurements

S = Sealed - filled in

U = Unused - exists but not used

Location

County, Township, Range, Section, 10-Acre plot

Depth

Depth (well to nearest ft)

Type log

D = driller's log

C = correlated log

S = sample study log

- = log not available

Year constructed

Year point source initially constructed

Driller

Well drilling contractor of well

ISWS 10-ACRE PLOT LOCATION SYSTEM


The following is an explanation of the ISWS Private Well Database location system.

The location system uses Township, Range, and Section. The location consists of five parts: County abbreviation, Township, Range, Section, and coordinate within the section (subsection or 10-acre plot). Sections are divided into rows of 1/8-mile squares. Each 1/8-mile square contains 10 acres and corresponds to a quarter of a quarter of a quarter section. A normal section of 1 square mile contains 8 rows of 1/8-mile squares; an odd-sized section contains more or fewer rows. Rows are numbered from east to west and lettered from south to north as shown in the diagram.

Example:

St. Clair County, FIP No. 163

T2N, R10W Section 23



The location of the well shown above is 163 2N10W-23.4c. The well point is located at the center of this 10-acre plot.

Illinois State Water Survey Private Well Database Page 1
Thursday Jun 29 19100 15:15:16

Query the Private Well Database through the World Wide Web http://gwinfo.sws.uiuc.edu/gwdb-query.html

County: Montgomery

Township Code: 8N Range Code: 4W Section Codes: 1

7 records were found for the specified locations.

Questions : Contact the Illinois State Water Survey's

Ground Water Division @ (217)333-9043

Publication: Please cite the Illinois State Water Survey's


Private-Well Database in all publications based wholly or partially on this information.

Please Note:

The data in the Private Well Inventory Database is a listing of those non-municipal wells which are known to the Illinois State Water Survey (ISWS). This information has been entered verbatim from well logs submitted by the driller, chemical analysis reports, well sealing forms, well inventory forms from the 1930-1934 well survey, and other special projects. The accuracy of this data is controlled by those who submitted the form. Information in the private well database has not been verified.

This data cannot be resold or redistributed. The Illinois State Water Survey must be acknowledged in any use of this material.

Location of 10-acre-plot within a Section



ILLINOIS STATE WATER SURVEY PRIVATE WELL DATABASE EXPLANATION

TWN TOWNSHIP
RNG RANGE
SC SECTION

PL PLOT LOCATION OWNER WELL OWNER

DRILLER WELL DRILLING CONTRACTOR OF WELL

DATE DATE INITIALLY DRILLED

PERMIT CODE LETTER INDICATED AGENCY

WHICH ISSUED PERMIT #

 M - MINES AND MINERALS (After 1988 Only Observation Wells And Irrigation Wells)

P - PUBLIC HEALTH (All Non-Community

Supplies)

E - EPA (Community Supplies)

N - NO FEE

X - UNDETERMINED

DEPTH REC DEPTH (Well To Nearest Ft)

RECORD TYPE (Types Of Information On File)

R - CONSTRUCTION REPORT

G - GEOLOGY S - SEALED A - AFFIDAVIT

C - CHEMICAL ANALYSIS

I - INVENTORY

X - INDICATES COMMENT IN OWNERS FIELD SOMETHING UNUSUAL

O - ANY OTHER TYPE OF RECORD

US

WELL USE - A TWO LETTER CODE INDICATING

THE USAGE OF THE WELL

CO - CONSERVATION

CS - COMMUNITY SUPPLY

DO - DOMESTIC

DW - DE-WATERING

IC - INDUSTRIAL/COMMERCIAL

IR - IRRIGATION

MO - MONITORING

NC - NON-COMMUNITY

OB - OBSERVATION

PK - PARK

RC - RECOVERY WELL

RW - RELIEF WELL



RECORD OF CONVERSATION


Route To: ____ Telephone Call (to/from) Meeting Address City, State, Zip_____ Discussion Summary


PE-21 (4/95)


RECORD OF CONVERSATION Route To:

Telephone Call (to/from)			
Meeting	tal Health		
Organization Montgomery County Environme	Date 6/30/00	Time090	00
Contact Robert Kirk	Title Director		
Ackdress	_Telephone Number	(217)53	2-2240
City, State, Zip Hills boro , Illinois			··
Project Name	Project Number		
REFERENCE Water Well Survey -	Engle 7in	<u>c</u>	
	<u> </u>		: .
Discussion Summary		· V	
Mr. Kirk has been with Mo.	regomery Co.	edy Envi	conmente!
Health for 34 years.	<i>J</i> /		
Mr. Kirk is not aware of a	iny private	e water i	sells
within 2,500 feet of Fagle	Zinc. M	ost if not	all
of the properties in Hills be			·
Schramm City are on f	sublic wexe	er. Publ	1,0
Water is obtained from	Lake Hills	boro.	
Montgomery County has be	en permitti	ng Idal	
water wells since January	1 1990.	Prior to	that
time, records were Kept	by the	State.	
	· · · · · ·	· · · · · · · · · · · · · · · · · · ·	
		· · · · · · · · · · · · · · · · · · ·	<u> </u>
		 	
LANGE OF THE PARTY		the strain of the	1 1 1 1 1 1 1 1 1 1
	eta en la companya de la companya d	在新聞作用。例如此	SOUTH THE

ATTACHMENT C
Historical Aerial Photographs











Location : Eagle Zinc Hillsboro, IL

Year: 1973

(Original photo hazy) Apprx. Scale : 1inch = 460 feet



If you have any questions call me at 1-800-767-0403

Order # 435508-749119 September 26, 2001





Location : Eagle Zinc Hillsboro, IL

Year: 1987

(Original photo hazy)
Apprx. Scale : 1inch = 700 feet



VISTA Information Solutions If you have any questions call me at 1-800-767-0403


Order # 435508-749119 September 26, 2001





Location : Eagle Zinc Hillsboro, IL Year : 1998

Apprx. Scale : 1inch = 590 feet



Order # 421907-369636 August 14, 2001 **ATTACHMENT D**Site History Timeline

	— 1912 Site initially de Products: zind	veloped for zinc processing under the name Lanyon Zinc Company. c, sulfuric acid	
	— 1919 Site purchase	d by Eagle-Picher Industries. Same products as Lanyon.	
	— 1935 Began manufa sulfuric acid pre	acture of zinc oxide and leaded zinc oxide. Ceased zinc smelting and oduction.	
	— 1958 Ceased produc	ction of leaded zinc oxide.	
		e purchased by The Sherwin-Williams Company.	
		nlly listed on CERCLIS as a Discovery Action. ninary Assessment conducted by IEPA.	
	- October 1993 CERC	CLA Expanded Site Inspection conducted by IEPA.	
	– May 1998 Site enter	ed into Interim Consent Order with IEPA.	
		oorts entitled Monitoring Well Installation and Ground Water Sampling Interim nd Interim Report of Residue Sampling and Analysis submitted to IEPA.	
-		Storm Water Permit No. IL 0074519 issued to Eagle Zinc Company.	
t	 Summer 2001 Engir December 31, 2001 	neered storm water retention pond constructed at Outfall 002. Eagle Zinc Parties enter into AOC with USEPA for completion of RI/FS.	
CNVIR	ON	Site History Timeline	Attachment

FRVIKOR
740 Waukegan Road, Suite 401, Deerfield, IL 60015

Site History Timelin Eagle Zinc Hillsboro, IL

D